

CALL ORDER : 311

CONTRACT ID : R -32881-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-85996 LIGHT STANDARD AND MAST ARM, REMOVE	10.000	EACH
12	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	2,060.000	CYS
14	205-03371 SEDIMENT, REMOVE	50.000	CYS
15	206-51235 COFFERDAM	LUMP	LUMP
16	207-08263 SUBGRADE TREATMENT, TYPE IA	9,459.000	SYS
17	210-06990 LIMESTONE	2.000	EACH
18	210-08138 RECEPTACLE	7.000	EACH
19	211-09264 STRUCTURAL BACKFILL, TYPE 1	4,527.000	CYS
20	211-09265 STRUCTURAL BACKFILL, TYPE 2	113.000	CYS
21	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	470.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	786.000	TON
23	302-06464 SUBBASE FOR PCCP	35.000	CYS
24	303-07662 STONE	60.880	TON
25	304-07490 HMA PATCHING, TYPE B	70.000	TON
26	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,327.000	SYS
27	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	579.000	TON
28	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	766.000	TON
29	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	1,226.000	TON
30	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	972.000	TON
31	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	906.000	TON
32	406-05520 ASPHALT FOR TACK COAT	7.000	TON
33	502-06329 PCCP, 12 IN	17.400	SYS
34	502-06999 PCCP, 8 IN	138.000	SYS
35	604-01527 PAVERS, BRICK	184.520	SYS
36	604-04452 LIMESTONE	125.600	CFT
37	604-06844 BRICK	354.940	SFT
38	604-07894 CURB RAMP, CONCRETE, A	38.000	SYS
39	604-07896 CURB RAMP, CONCRETE, B	28.000	SYS
40	604-07901 CURB RAMP, CONCRETE, G	12.000	SYS
41	604-07904 CURB RAMP, CONCRETE, L	12.000	SYS
42	604-91531 SIDEWALK, CONCRETE, 4 IN	3,540.000	SYS
43	605-06120 CURB, CONCRETE	1,855.000	LFT
44	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	3,489.000	LFT
45	605-06160 CURB AND GUTTER, B, CONCRETE, MODIFIED	85.000	LFT
46	605-06160 CURB AND GUTTER, B, CONCRETE, MODIFIED	50.000	LFT
47	615-06505 MONUMENT, B	8.000	EACH
48	616-02320 GEOTEXTILES	29.000	SYS
49	616-06405 RIPRAP, REVETMENT	12.000	TON

CALL ORDER : 311

CONTRACT ID : R -32881-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
51	621-06545 FERTILIZER	0.210	TON
52	621-06557 SEED MIXTURE, T	80.000	LBS
53	621-06565 MULCHING MATERIAL	1.000	TON
54	621-06567 WATER	9.000	KGAL
55	621-06570 TOPSOIL	612.000	CYS
56	621-06575 SODDING, NURSERY	2,563.000	SYS
57	621-90853 TAPPING SLEEVE WITH VALVE	2.000	EACH
58	628-09401 FIELD OFFICE, A	6.000	MOS
59	702-01724 CONCRETE, C, FOOTINGS	33.440	CYS
60	702-76240 CONCRETE	21.420	CYS
61	703-06028 REINFORCING BARS	440.710	LBS
62	715-02529 VALVE WITH BOX, RESTRAINED, BUTTERFLY, DUCTILE	8.000	EACH
63	715-03169 WATER MAIN, DUCTILE IRON, 14 IN	43.000	LFT
64	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	3,334.000	LFT
65	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	1,177.000	LFT
66	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	595.000	LFT
67	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN	448.000	LFT
68	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN	237.000	LFT
69	715-05161 PIPE, TYPE 2, CIRCULAR, 48 IN	186.000	LFT
70	715-08048 STORMWATER TREATMENT SYSTEM	1.000	EACH
71	715-08048 STORMWATER TREATMENT SYSTEM	1.000	EACH
72	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	83.000	TON
73	715-09836 INSULATION	20,514.000	CFT
74	715-09883 VALVE WITH BOX	2.000	EACH
75	715-91738 WATER MAIN, DUCTILE IRON, 6 IN	143.000	LFT
76	715-91739 WATER MAIN, DUCTILE IRON, 8 IN	132.000	LFT
77	715-92544 WATER MAIN, DUCTILE IRON, 12 IN	132.000	LFT
78	715-92544 WATER MAIN, DUCTILE IRON, 12 IN	53.000	LFT
79	715-94064 WATER LINE, COPPER, 0.75 IN	663.740	LFT
80	715-96669 WATER MAIN, DUCTILE IRON, 16 IN	3,291.000	LFT
81	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
82	718-52610 AGGREGATE FOR UNDERDRAINS	300.000	CYS
83	718-99153 GEOTEXTILES FOR UNDERDRAIN	3,734.000	SYS
84	720-45045 INLET, J10	17.000	EACH
85	720-45055 INLET, M10	17.000	EACH
86	720-45410 MANHOLE, C4	13.000	EACH
87	720-93501 MANHOLE, L4	1.000	EACH
88	720-95422 MANHOLE, J4	1.000	EACH
89	720-98625 MANHOLE, C4, DROP	4.000	EACH
90	732-01898 WATER MAIN, DUCTILE IRON, 10 IN	611.000	LFT
91	732-02433 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON, 12 IN.	2.000	EACH
92	732-02531 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON 6 IN.	4.000	EACH
93	732-02532 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON, 8 IN.	2.000	EACH
94	732-09202 VALVE WITH BOX, RESTRAINED, GATE,	2.000	EACH
95	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
96	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
97	801-06625 DETOUR ROUTE MARKER ASSEMBLY	10.000	EACH
98	801-06640 CONSTRUCTION SIGN, A	10.000	EACH

CALL ORDER : 311

CONTRACT ID : R -32881-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
99	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
100	801-07119 BARRICADE, III-B	165.000	LFT
101	802-04314 SIGN	2.000	EACH
102	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	130.000	LFT
103	802-07127 SIGN, DOUBLE-FACED SHEET ENCAPSULATED LENS,	10.500	SFT
104	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	199.160	SFT
105	805-04973 CONDUIT	5,211.830	LFT
106	805-04973 CONDUIT	119.160	LFT
107	805-86900 JUNCTION BOX	10.000	EACH
108	807-04651 WIRE,	218.640	LFT
109	807-04651 WIRE,	1,728.820	LFT
110	807-04651 WIRE,	14,762.610	LFT
111	807-04652 SERVICE POINT	1.000	EACH
112	807-04654 LIGHT POLE	10.000	EACH
113	807-04654 LIGHT POLE	1.000	EACH
114	807-04779 CONCRETE FOUNDATION WITH GROUNDING	34.000	EACH
115	807-04866 LUMINAIRE	33.000	EACH
116	807-04962 LIGHT	4.000	EACH
117	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	28.000	LFT
118	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	245.000	LFT
119	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,333.000	LFT
120	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	77.000	LFT
121	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	740.000	LFT
122	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	4.000	EACH
123	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	2.000	EACH
124	808-92027 LINE, THERMO, SOLID, YELLOW, 8 IN	1,444.000	LFT