

CALL ORDER : 170

CONTRACT ID : R -29276-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-05545 REGULATED MATERIALS, DISPOSE, C	680.000	CYS
11	202-05550 REGULATED MATERIALS, REMOVE, C	680.000	CYS
12	202-05555 REGULATED MATERIALS, TRANSPORT, C	680.000	CYS
13	202-07603 TESTING FOR WASTE, C	30.000	EACH
14	203-02000 EXCAVATION, COMMON	1,051.000	CYS
15	203-02020 EXCAVATION, UNCLASSIFIED	520.000	CYS
16	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	10.000	EACH
17	207-08263 SUBGRADE TREATMENT, TYPE IA	3,242.000	SYS
18	207-08267 SUBGRADE TREATMENT, TYPE IIIA	692.000	SYS
19	211-09264 STRUCTURAL BACKFILL, TYPE 1	22.000	CYS
20	211-09264 STRUCTURAL BACKFILL, TYPE 1	129.000	CYS
21	303-01180 COMPACTED AGGREGATE, NO. 53	258.000	TON
22	304-07494 WIDENING WITH HMA, TYPE C	271.000	TON
23	306-08033 MILLING, ASPHALT, 1 IN	1,053.000	SYS
24	306-08036 MILLING, ASPHALT, 2 IN	5,088.000	SYS
25	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	621.000	TON
26	401-07379 QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm	828.000	TON
27	402-07442 HMA BASE, TYPE C	596.000	TON
28	406-05520 ASPHALT FOR TACK COAT	12.500	TON
29	604-07896 CURB RAMP, CONCRETE, B	33.000	SYS
30	604-91531 SIDEWALK, CONCRETE, 4 IN	576.000	SYS
31	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	2,125.000	LFT
32	610-08446 PCCP FOR APPROACHES, 6 IN	83.000	SYS
33	610-09108 PCCP FOR APPROACHES, 9 IN	611.000	SYS
34	615-06505 MONUMENT, B	8.000	EACH
35	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
36	621-06567 WATER	1.700	KGAL
37	621-06574 SODDING	418.000	SYS
38	628-09401 FIELD OFFICE, A	6.000	MOS
39	702-51015 CONCRETE, B, FOOTINGS	15.000	CYS
40	702-90915 CONCRETE, CLASS A	17.000	CYS
41	703-06028 REINFORCING BARS	3,070.000	LBS
42	709-07733 ANTI-GRAFFITI COAT	LUMP	LUMP
43	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	74.000	LFT
44	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
45	720-44296 CAP INLET	5.000	EACH
46	720-45045 INLET, J10	1.000	EACH
47	720-45145 INLET, J10, MODIFIED	4.000	EACH
48	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	4.000	EACH
49	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	12,357.000	LFT

CALL ORDER : 170

CONTRACT ID : R -29276-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	4.000	EACH
51	801-06577 TEMPORARY PAVEMENT MARKING	88.000	LFT
52	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
53	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
54	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
55	801-07118 BARRICADE, III-A	96.000	LFT
56	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	83.000	LFT
57	802-07060 SIGN, SHEET, RELOCATE	7.000	EACH
58	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	67.300	SFT
59	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
60	805-01815 SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN	4.000	EACH
61	805-01842 HANDHOLE, SIGNAL	5.000	EACH
62	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
63	805-02150 PEDESTRIAN SIGNAL HEAD, 18 IN	8.000	EACH
64	805-09471 SIGNAL CABLE, PREFORMED PAVE-OVER LOOP	51.000	EACH
65	805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, 2 CHANNEL	8.000	EACH
66	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
67	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	8.000	EACH
68	805-78370 PEDESTRIAN PUSH BUTTON	8.000	EACH
69	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
70	805-78420 DISCONNECT HANGER	4.000	EACH
71	805-78445 SIGNAL SERVICE	1.000	EACH
72	805-78467 SIGNAL CABLE, 3C 8GA	34.100	LFT
73	805-78480 SIGNAL CABLE, 3C 14GA	1,427.200	LFT
74	805-78485 SIGNAL CABLE, 5C 14GA	1,561.600	LFT
75	805-78490 SIGNAL CABLE, 7C 14GA	702.500	LFT
76	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,616.800	LFT
77	805-78785 SIGNAL DETECTOR HOUSING	15.000	EACH
78	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
79	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	4.000	EACH
80	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHAN	2.000	EACH
81	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	564.400	LFT
82	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	764.000	LFT
83	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,095.000	LFT
84	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,386.000	LFT
85	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	171.000	LFT
86	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	709.000	LFT
87	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	5.000	EACH
88	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	2.000	EACH

CALL ORDER : 366

CONTRACT ID : R -33063-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LANDSCAPING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
8	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	500.000	TON
9	205-06933 TEMP DITCH INLET PROTECTION	23.000	EACH
10	205-06937 TEMPORARY SILT FENCE	4,623.000	LFT
11	205-08594 FILTER SOCK	15,228.000	LFT
12	205-09543 NO 2 STONE	788.000	TON
13	616-06451 RIPRAP, UNIFORM	335.000	TON
14	616-06451 RIPRAP, UNIFORM	246.000	TON
15	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
16	621-06559 MULCHED SEEDING, R	9,866.000	SYS
17	621-06567 WATER	8,500.000	KGAL
18	621-09902 SOIL LAB TESTING	60.000	EACH
19	621-09903 PERCOLATION TEST	134.000	EACH
20	621-09904 DENSITY TEST	134.000	EACH
21	621-09905 SULFUR	4,099.000	LBS
22	621-09906 SEED MIXTURE, PRAIRIE SEED	5.220	ACRE
23	621-09907 STAGING PLAN AND PREPARATION	LUMP	LUMP
24	621-09908 SOIL	6,096.000	CYS
25	621-09908 SOIL	76.000	CYS
26	621-09909 SOIL	53,369.000	SYS
27	621-09909 SOIL	38,402.000	SYS
28	621-09909 SOIL	53,369.000	SYS
29	621-98038 MULCH, HARDWOOD SHREDDED BARK	2,658.000	CYS
30	622-52436 SIGN, DO NOT MOW OR SPRAY	138.000	EACH
31	624-92647 HERBICIDE TREATMENT	11.410	ACRE
32	702-03607 CORED HOLE IN CONCRETE	13.000	EACH
33	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	5,357.000	LFT
34	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN	330.000	LFT
35	718-06529 OUTLET PROTECTOR, 2	11.000	EACH
36	718-52610 AGGREGATE FOR UNDERDRAINS	404.000	CYS
37	801-03290 CONSTRUCTION SIGN, C	33.000	EACH
38	801-06625 DETOUR ROUTE MARKER ASSEMBLY	27.000	EACH
39	801-06640 CONSTRUCTION SIGN, A	177.000	EACH
40	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
41	801-07118 BARRICADE, III-A	216.000	LFT
42	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
43	802-04314 SIGN	298.000	EACH

CALL ORDER : 676

CONTRACT ID : B -30996-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	173.000	SYS
11	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
12	202-51822 BRIDGE DECK OVERLAY, REMOVE	1,157.000	SYS
13	202-94954 BARRIER WALL, CONCRETE, REMOVE	270.000	LFT
14	302-07455 DENSE GRADED SUBBASE	32.000	CYS
15	306-08043 MILLING, TRANSITION	500.000	SYS
16	406-05521 ASPHALT FOR TACK COAT	500.000	SYS
17	502-06329 PCCP, 12 IN	81.000	SYS
18	503-03489 RETROFITTED TIE BARS	36.000	EACH
19	503-05310 TERMINAL JOINT	46.000	LFT
20	601-01522 GUARDRAIL TRANSITION TYPE TGB	1.000	EACH
21	601-02241 GUARDRAIL, REMOVE	380.000	LFT
22	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
23	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	363.000	LFT
24	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	124.000	SYS
25	610-07488 HMA FOR APPROACHES, TYPE C	42.000	TON
26	628-09401 FIELD OFFICE, A	5.000	MOS
27	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	5.000	MOS
28	702-51005 CONCRETE, A, SUBSTRUCTURE	6.800	CYS
29	702-51863 FIELD DRILLED HOLE IN CONCRETE	846.000	EACH
30	703-01719 CATHODIC PROTECTION SYSTEM	LUMP	LUMP
31	703-06028 REINFORCING BARS	41,852.000	LBS
32	703-06029 REINFORCING BARS, EPOXY COATED	12,383.000	LBS
33	703-96512 BAR SPLICE	4,068.000	EACH
34	704-51006 CONCRETE, C, SUPERSTRUCTURE, MODIFIED	174.300	CYS
35	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	1.000	EACH
36	706-51020 CONCRETE, C, RAILING	41.400	CYS
37	707-01065 POST-TENSIONING	LUMP	LUMP
38	709-51821 SURFACE SEAL	LUMP	LUMP
39	715-09938 PIPE, BRIDGE DECK DRAIN SYSYEM	528.000	LFT
40	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
41	722-51842 BRIDGE DECK OVERLAY	1,727.000	SYS
42	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	50.000	SFT
43	724-51925 STRUCTURAL EXPANSION JOINT, SS	57.000	LFT
44	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
45	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
46	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
47	805-01815 SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN	2.000	EACH
48	808-74809 PAVEMENT MESSAGE MARKING, EPOXY, (R X R)	4.000	EACH

