

CALL ORDER : 171

CONTRACT ID : IR-33737-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION, HMA		
1	207-08263 SUBGRADE TREATMENT, TYPE IA	138,445.000	SYS
2	211-09264 STRUCTURAL BACKFILL, TYPE 1	3,760.000	CYS
3	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	23,751.000	TON
4	303-01180 COMPACTED AGGREGATE, NO. 53	9,413.000	TON
5	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	4,613.000	TON
6	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	14,708.000	TON
7	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	3,542.000	TON
8	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	22,410.000	TON
9	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	12,551.000	TON
10	401-07422 QC/QA-HMA, 1, 64, BASE, 19.0 mm	4,959.000	TON
11	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	24,453.000	TON
12	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	57,903.000	TON
13	406-05520 ASPHALT FOR TACK COAT	231.000	TON
14	606-07484 MILLED HMA SHOULDER CORRUGATIONS	98,800.000	LFT
15	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	6,586.000	LFT
16	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	6,223.000	LFT
17	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	33,716.000	LFT
18	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	1,384.000	LFT
19	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	1,384.000	LFT
20	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	33,716.000	LFT
SECTION NO. 0002	NEW ROAD CONSTRUCTION, PCCP		
21	207-08263 SUBGRADE TREATMENT, TYPE IA	141,723.000	SYS
22	211-09264 STRUCTURAL BACKFILL, TYPE 1	3,712.000	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	15,089.000	TON
24	302-06464 SUBBASE FOR PCCP	41,971.000	CYS
25	303-01180 COMPACTED AGGREGATE, NO. 53	6,569.000	TON
26	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	5,480.000	TON
27	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	10,842.000	TON
28	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	13,055.000	TON
29	406-05520 ASPHALT FOR TACK COAT	40.000	TON
30	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
31	501-06727 CORING, PCCP	LUMP	LUMP
32	501-08193 QC/QA-PCCP, 10.5 IN	142,311.000	SYS
33	501-10254 QC/QA PCCP, 8.5"	25,571.000	SYS
34	503-05240 D-1 CONTRACTION JOINT	102,280.000	LFT
35	503-05310 TERMINAL JOINT	257.000	LFT
36	606-07484 MILLED HMA SHOULDER CORRUGATIONS	23,600.000	LFT
37	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	72,710.000	LFT
38	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	6,020.000	LFT
39	718-99153 GEOTEXTILES FOR UNDERDRAIN	37,015.000	SYS
40	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8,824.000	LFT
41	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	26,276.000	LFT
42	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	26,276.000	LFT
43	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	6,450.000	LFT
44	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	8,824.000	LFT
SECTION NO. 0003	NEW ROAD CONSTRUCTION, HMA		

CALL ORDER : 171

CONTRACT ID : IR-33737-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW ROAD CONSTRUCTION, HMA			
45	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	2,781.000 TON
46	303-01180	COMPACTED AGGREGATE, NO. 53	3,811.000 TON
47	401-06264	PROFILOGRAPH, HMA	LUMP LUMP
48	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,329.000 TON
49	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	2,289.000 TON
50	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	5,460.000 TON
51	401-07429	QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	2,296.000 TON
52	402-07440	HMA BASE, TYPE A	1,114.000 TON
53	406-05520	ASPHALT FOR TACK COAT	16.000 TON
54	615-06505	MONUMENT, B	10.000 EACH
55	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN	782.000 LFT
56	718-99153	GEOTEXTILES FOR UNDERDRAIN	6,991.000 SYS
57	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	9,655.000 LFT
58	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	9,778.000 LFT
59	808-75278	TRANSVERSE MARKING, THERMOPLASTIC,	30.000 LFT
60	808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	127.000 LFT
61	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000 EACH
62	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000 EACH
63	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	334.000 LFT
SECTION NO. 0004 NEW ROAD CONSTRUCTION, PCCP			
64	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	1,679.000 TON
65	302-06464	SUBBASE FOR PCCP	4,861.000 CY
66	303-01180	COMPACTED AGGREGATE, NO. 53	1,981.000 TON
67	402-07435	HMA INTERMEDIATE, TYPE A	775.000 TON
68	402-07440	HMA BASE, TYPE A	496.000 TON
69	406-05520	ASPHALT FOR TACK COAT	4.000 TON
70	501-06266	PROFILOGRAPH, PCCP	LUMP LUMP
71	501-06727	CORING, PCCP	LUMP LUMP
72	501-10254	QC/QA PCCP, 8.5"	16,107.000 SYS
73	503-05240	D-1 CONTRACTION JOINT	9,309.000 LFT
74	615-06515	MONUMENT, D	10.000 EACH
75	703-06028	REINFORCING BARS	42.000 LBS
76	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN	757.000 LFT
77	718-99153	GEOTEXTILES FOR UNDERDRAIN	7,314.000 SYS
78	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,050.000 LFT
79	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	8,605.000 LFT
80	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	7,498.000 LFT
81	808-10042	TRANSVERSE MARKING MULTI-COMPONENT,	30.000 LFT
82	808-10051	TRANSVERSE MARKING MULTI-COMPONENT,	103.000 LFT
83	808-10052	PAVEMENT MESSAGE MKG, MULTI-COMP, (ONLY)	2.000 EACH
84	808-10058	LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN	334.000 LFT
85	808-10077	PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	2.000 EACH
86	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	2,280.000 LFT
87	808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	24.000 LFT
SECTION NO. 0005 NEW ROAD CONSTRUCTION			

CALL ORDER : 171

CONTRACT ID : IR-33737-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	NEW ROAD CONSTRUCTION		
88	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
89	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION, CPM SCHEDULE	LUMP	LUMP
90	108-09283 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
91	110-01001 CLEARING RIGHT OF WAY	LUMP	LUMP
92	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
93	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
94	201-52370 PAVEMENT REMOVAL	7,330.000	SYS
95	202-02240 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
96	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
97	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
98	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
99	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
100	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
101	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
102	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
103	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
104	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
105	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
106	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
107	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
108	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
109	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
110	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
111	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
112	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
113	202-74080 OVERHEAD SIGN STRUCTURE,	1.000	EACH
114	203-02020 EXCAVATION, UNCLASSIFIED	4,233,477.000	CYS
115	203-02055 EMBANKMENT	54,852.000	CYS
116	203-02070 BORROW	344,187.000	CYS
117	203-09567 SPILL CONTAINMENT DAM	12.000	EACH
118	203-11329 LIGHT WEIGHT DEFLECTOMETER	2.000	EACH
119	204-02290 SETTLEMENT PLATE	4.000	EACH
120	204-08414 STAKE, LATERAL	8.000	EACH
121	204-08415 STAKE, SETTLEMENT	9.000	EACH
122	204-08552 VIBRATING WIRE SETTLEMENT SYSTEM	7.000	EACH
123	205-02770 EROSION CONTROL BLANKET	1,620.000	SYS
124	205-06935 TEMPORARY SEDIMENT BASIN	41.000	EACH
125	205-09952 DESIGN BUILD EROSION AND SEDIMENT CONTROL	LUMP	LUMP
126	206-51215 EXCAVATION, X	136.000	CYS
127	206-51220 EXCAVATION, WET	2,400.000	CYS
128	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	3,874.000	CYS
129	207-08263 SUBGRADE TREATMENT, TYPE IA	156,747.000	SYS
130	207-08265 SUBGRADE TREATMENT, TYPE IIA	19,628.000	SYS
131	207-08267 SUBGRADE TREATMENT, TYPE IIIA	7,982.000	SYS
132	211-02050 B BORROW	4,656.000	CYS
133	211-06467 AGGREGATE FOR END BENT BACKFILL	483.300	CYS
134	211-09264 STRUCTURAL BACKFILL, TYPE 1	6,861.000	CYS
135	211-09265 STRUCTURAL BACKFILL, TYPE 2	13,904.000	CYS
136	211-09266 STRUCTURAL BACKFILL, TYPE 3	8,297.000	CYS

CALL ORDER : 171

CONTRACT ID : IR-33737-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005 NEW ROAD CONSTRUCTION			
137	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	320.000 TON
138	302-07455	DENSE GRADED SUBBASE	276.900 CYS
139	302-08562	COARSE AGGREGATE, 8	1.000 TON
140	303-01180	COMPACTED AGGREGATE, NO. 53	20,634.000 TON
141	303-02172	TEMPORARY AGGREGATE	1,838.000 TON
142	303-07449	COMPACTED AGGREGATE, NO. 73	375.000 TON
143	303-07662	STONE	297.000 TON
144	304-07493	WIDENING WITH HMA, TYPE B	73.000 TON
145	306-08043	MILLING, TRANSITION	3,034.000 SYS
146	401-06264	PROFILOGRAPH, HMA	LUMP LUMP
147	401-07320	QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	11.000 TON
148	401-07389	QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	22.000 TON
149	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	3,577.000 TON
150	402-07432	HMA SURFACE, TYPE A	1,158.000 TON
151	402-07433	HMA SURFACE, TYPE B	924.000 TON
152	402-07434	HMA SURFACE, TYPE C	127.000 TON
153	402-07435	HMA INTERMEDIATE, TYPE A	773.000 TON
154	402-07438	HMA INTERMEDIATE, TYPE B	1,512.000 TON
155	402-07453	HMA FOR TEMPORARY PAVEMENT, TYPE	140.000 TON
156	402-07453	HMA FOR TEMPORARY PAVEMENT, TYPE	633.000 TON
157	406-05520	ASPHALT FOR TACK COAT	3.900 TON
158	601-01522	GUARDRAIL, TRANSITION TYPE TGB	20.000 EACH
159	601-01848	GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 5	1.000 EACH
160	601-05585	GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 8	1.000 EACH
161	601-06037	GUARDRAIL END TREATMENT, I	8.000 EACH
162	601-06233	IMPACT ATTENUATOR, ED, W1, TL-3	4.000 EACH
163	601-06777	GRAVEL BARREL ARRAY	2.000 EACH
164	601-94689	GUARDRAIL END TREATMENT, OS	20.000 EACH
165	601-94690	GUARDRAIL END TREATMENT, MS	4.000 EACH
166	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	22,943.000 LFT
167	601-99108	GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	1,154.500 LFT
168	602-06729	BARRIER DELINEATOR	140.000 EACH
169	603-06040	FENCE, FARM FIELD, 47 IN	59,880.000 LFT
170	603-96042	FENCE GATE, FARM FIELD, 47 IN X 24FT	4.000 EACH
171	605-06121	CURB, CONCRETE, B	273.000 LFT
172	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	150.000 SYS
173	609-06259	REINFORCED CONCRETE BRIDGE APPROACH 12 IN	1,510.500 SYS
174	610-07486	HMA FOR APPROACHES, TYPE A	166.000 TON
175	610-07487	HMA FOR APPROACHES, TYPE B	2,348.000 TON
176	611-06497	MAILBOX ASSEMBLY, SINGLE	20.000 EACH
177	611-07052	PREFORMED JOINT MATERIAL	136.000 LFT
178	615-06490	RIGHT OF WAY MARKER	105.000 EACH
179	615-06505	MONUMENT, B	15.000 EACH
180	615-06510	MONUMENT, C	45.000 EACH
181	615-06515	MONUMENT, D	32.000 EACH
182	615-06527	MONUMENT, SECTION CORNER	3.000 EACH
183	615-06530	BENCH MARK POST	8.000 EACH
184	616-02320	GEOTEXTILES	175,705.000 SYS
185	616-05688	RIPRAP, CLASS 1	6,925.000 TON

CALL ORDER : 171

CONTRACT ID : IR-33737-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005 NEW ROAD CONSTRUCTION			
186	616-05689 RIPRAP, CLASS 2	689.000	TON
187	616-06405 RIPRAP, REVETMENT	62,456.000	TON
188	616-51367 SLOPEWALL, CONCRETE, 4 IN	1,693.500	SYS
189	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	14.000	EACH
190	621-02770 EROSION CONTROL BLANKET	12,153.000	SYS
191	621-04258 SEED MIXTURE	43.100	LBS
192	621-04258 SEED MIXTURE	48.000	LBS
193	621-06545 FERTILIZER	79.700	TON
194	621-06553 SEED MIXTURE, R	36,375.000	LBS
195	621-06557 SEED MIXTURE, T	9,713.000	LBS
196	621-06559 MULCHED SEEDING, R	20,425.000	SYS
197	621-06565 MULCHING MATERIAL	429.400	TON
198	621-06567 WATER	265.000	KGAL
199	621-06570 TOPSOIL	4,333.000	CYS
200	621-06574 SODDING	72,680.000	SYS
201	621-52448 SIGN, DO NOT SPRAY	100.000	EACH
202	622-10003 LIVE PLANT STAKING	528.000	EACH
203	622-52436 SIGN, DO NOT MOW OR SPRAY	15.000	EACH
204	622-91786 SEEDLING	245.000	EACH
205	622-91786 SEEDLING	418.000	EACH
206	628-09403 FIELD OFFICE, C	20.000	MOS
207	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	100.000	MOS
208	628-11068 CELLULAR TELEPHONE/RADIO	6.000	EACH
209	628-11069 CELLULAR TELEPHONE/RADIO SERVICE, ANYTIME MINUTES	120.000	MOS
210	701-02938 CORED HOLE IN ROCK, 24 IN	404.000	LFT
211	701-05561 DRILLED SHAFT	1,210.000	LFT
212	701-05561 DRILLED SHAFT	474.000	LFT
213	701-05561 DRILLED SHAFT	445.000	LFT
214	701-05561 DRILLED SHAFT	222.000	LFT
215	701-05781 UNCLASSIFIED SHAFT EXCAVATION	819.500	CYS
216	701-05782 UNCLASSIFIED EXTRA DEPTH EXCAVATION	33.800	CYS
217	701-05783 OBSTRUCTIONS	40.000	HRS
218	701-05785 EXPLORATION (SHAFT EXCAVATION)	1,170.000	LFT
219	701-05787 INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION	LUMP	LUMP
220	701-05787 INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION	LUMP	LUMP
221	701-05787 INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION	LUMP	LUMP
222	701-05787 INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION	LUMP	LUMP
223	701-06011 DYNAMIC PILE LOAD TEST	6.000	EACH
224	701-09557 TEST PILE, DYNAMIC, PRODUCTION	355.000	LFT
225	701-09559 TEST PILE, DYNAMIC, RESTRIKE	6.000	EACH
226	701-09683 PILE SHOE, HP 12 X 74	120.000	EACH
227	701-95780 PILE, STEEL H, HP 12 IN X 74	4,852.000	LFT
228	702-01724 CONCRETE, C, FOOTINGS	1,011.400	CYS
229	702-51005 CONCRETE, A, SUBSTRUCTURE	754.900	CYS
230	702-51015 CONCRETE, B, FOOTINGS	87.700	CYS
231	702-92857 CONCRETE, C, SUBSTRUCTURE	3,812.800	CYS
232	702-95467 ROADWAY DRAIN	6.000	EACH
233	703-06028 REINFORCING BARS	710,833.000	LBS
234	703-06029 REINFORCING BARS, EPOXY COATED	1,438,098.000	LBS

CALL ORDER : 171

CONTRACT ID : IR-33737-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005 NEW ROAD CONSTRUCTION			
235	704-51002 CONCRETE, C, SUPERSTRUCTURE	3,967.800	CYS
236	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	8.000	EACH
237	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	16.000	EACH
238	706-51020 RAILING, CONCRETE, C	577.700	CYS
239	707-07605 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 54 IN X 48 IN	762.000	LFT
240	707-08158 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 42 IN X 49 IN	937.000	LFT
241	707-09332 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 66 IN X 48 IN	8,004.600	LFT
242	709-51821 SURFACE SEAL	LUMP	LUMP
243	709-51821 SURFACE SEAL	LUMP	LUMP
244	709-51821 SURFACE SEAL	LUMP	LUMP
245	709-51821 SURFACE SEAL	LUMP	LUMP
246	709-51821 SURFACE SEAL	LUMP	LUMP
247	709-51821 SURFACE SEAL	LUMP	LUMP
248	711-96800 STUD SHEAR CONNECTORS	744.000	EACH
249	713-04509 TEMPORARY PIPE	LUMP	LUMP
250	714-11177 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	90.000	LFT
251	714-11179 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	280.000	LFT
252	714-11183 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	328.000	LFT
253	714-11187 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	376.000	LFT
254	714-11193 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	242.000	LFT
255	714-11303 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	74.000	LFT
256	715-01471 PIPE END SECTION, PRECAST CONCRETE, 15 IN	14.000	EACH
257	715-01472 PIPE END SECTION, PRECAST CONCRETE, 18 IN	7.000	EACH
258	715-01765 PIPE END SECTION, PRECAST CONCRETE, 12 IN	2.000	EACH
259	715-04632 PIPE END SECTION, PRECAST CONCRETE, 36 IN.	10.000	EACH
260	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	852.000	LFT
261	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	128,630.000	LFT
262	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	26,526.000	LFT
263	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	4,044.000	LFT
264	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	74.000	LFT
265	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	103.000	LFT
266	715-05127 PIPE, TYPE 1 CIRCULAR 42 IN	692.000	LFT
267	715-05129 PIPE, TYPE 1 CIRCULAR 54 IN	347.000	LFT
268	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	273.000	LFT
269	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	1,253.000	LFT
270	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	2,682.000	LFT
271	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	285.000	LFT
272	715-05161 PIPE, TYPE 2 CIRCULAR 48 IN	448.000	LFT
273	715-05165 PIPE, TYPE 2 CIRCULAR 72 IN	306.000	LFT
274	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	369.000	LFT
275	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	69.000	LFT
276	715-05173 PIPE, TYPE 3 CIRCULAR 24 IN	188.000	LFT
277	715-05217 PIPE, TYPE 5 CIRCULAR 12 IN	240.000	LFT
278	715-05229 PIPE, TYPE 1 DEFORMED MIN AREA 1.8 SF	56.000	LFT
279	715-05407 PIPE, END BENT DRAIN, 6 IN	607.000	LFT
280	715-05842 CONCRETE ANCHOR 42 IN	4.000	EACH
281	715-06004 CONCRETE ANCHOR, 48 IN	4.000	EACH
282	715-06357 CONCRETE ANCHOR, 72 IN	2.000	EACH
283	715-06492 CONCRETE ANCHOR, 54 IN	4.000	EACH

CALL ORDER : 171

CONTRACT ID : IR-33737-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	NEW ROAD CONSTRUCTION		
284	715-09938 PIPE, BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
285	715-09938 PIPE, BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
286	715-46005 PIPE END SECTION, 15 IN	20.000	EACH
287	715-46010 PIPE END SECTION, 18 IN	26.000	EACH
288	715-46020 PIPE END SECTION, 24 IN	13.000	EACH
289	715-96389 PIPE END SECTION, PRECAST CONCRETE, 24 IN	4.000	EACH
290	718-06528 OUTLET PROTECTOR, 1	153.000	EACH
291	718-06529 OUTLET PROTECTOR, 2	161.000	EACH
292	718-06531 OUTLET PROTECTOR, 3	17.000	EACH
293	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	16,000.000	LFT
294	718-52610 AGGREGATE FOR UNDERDRAINS	11,336.000	CYS
295	718-99153 GEOTEXTILES FOR UNDERDRAIN	67,833.000	SYS
296	720-45065 INLET, N12	45.000	EACH
297	720-45070 INLET, P12A	2.000	EACH
298	720-45130 INLET, E7, MODIFIED	1.000	EACH
299	720-93443 INLET, U	1.000	EACH
300	720-94525 INLET, W	1.000	EACH
301	720-95310 INLET, P12A, MODIFIED	1.000	EACH
302	723-11203 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	414.000	LFT
303	723-11226 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	90.000	LFT
304	723-11330 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	407.000	LFT
305	723-11333 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	500.000	LFT
306	731-08252 LEVELING PAD	336.000	LFT
307	731-93945 FACE PANELS, CONCRETE	11,339.000	SFT
308	731-93946 WALL ERECTION	11,339.000	SFT
309	731-93947 LEVELING PAD, CONCRETE	306.000	LFT
310	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
311	801-03290 CONSTRUCTION SIGN, C	9.000	EACH
312	801-03291 CONSTRUCTION SIGN, D	5.000	EACH
313	801-04308 ROAD CLOSURE SIGN ASSEMBLY	16.000	EACH
314	801-06199 ROAD CLOSURE SIGN ASSEMBLY, PERMANENT	2.000	EACH
315	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	4,850.000	LFT
316	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	3,085.000	LFT
317	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	24.000	LFT
318	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	4.000	EACH
319	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	63.000	LFT
320	801-06625 DETOUR ROUTE MARKER ASSEMBLY	60.000	EACH
321	801-06640 CONSTRUCTION SIGN, A	43.000	EACH
322	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
323	801-06650 TEMPORARY RAISED PAVEMENT MARKER, 2	40.000	EACH
324	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
325	801-07118 BARRICADE, III-A	180.000	LFT
326	801-07119 BARRICADE, III-B	552.000	LFT
327	801-07120 BARRICADE, III, PERMANENT	132.000	LFT
328	801-09087 TEMPORARY PAVEMENT MARKING, REMOVABLE, 12 IN	117.000	LFT
329	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	3.000	EACH
330	801-97643 TEMPORARY BUZZ STRIPS	288.000	LFT
331	802-04893 REFERENCE POST	18.000	EACH
332	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	909.000	LFT

CALL ORDER : 171

CONTRACT ID : IR-33737-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	NEW ROAD CONSTRUCTION		
333	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	54.000	LFT
334	802-05706 SIGN POST, SQUARE, TYPE 3, UNREINFORCED ANCHOR BASE	99.000	LFT
335	802-07057 SIGN, PANEL, WITH LEGEND	1,108.500	SFT
336	802-07060 SIGN, SHEET, RELOCATE	3.000	EACH
337	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	6.000	EACH
338	802-08456 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII	14.000	EACH
339	802-09577 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE E	2.000	EACH
340	802-09581 OVERHEAD BALANCED CANTILEVER SIGN STRUCTURE FOUNDATION,	2.000	EACH
341	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	421.350	SFT
342	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS	317.500	SFT
343	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	73.500	SFT
344	802-76095 STRUCTURAL STEEL, BREAKAWAY	4,208.000	LBS
345	804-06770 DELINEATOR POST	100.000	EACH
346	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
347	805-01815 SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN	4.000	EACH
348	805-01842 HANDHOLE, SIGNAL	10.000	EACH
349	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	1,530.000	LFT
350	805-01879 SIGNAL SERVICE, INSTALL	1.000	EACH
351	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
352	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
353	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	6.000	EACH
354	805-78420 DISCONNECT HANGER	3.000	EACH
355	805-78467 SIGNAL CABLE, 3C/8GA	30.000	LFT
356	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	2,610.000	LFT
357	805-78485 SIGNAL CABLE, 5C/14GA	130.000	LFT
358	805-78490 SIGNAL CABLE, 7C/14GA	760.000	LFT
359	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	2,320.000	LFT
360	805-78785 SIGNAL DETECTOR HOUSING	7.000	EACH
361	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,070.000	LFT
362	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
363	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT	4.000	EACH
364	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	9.000	EACH
365	808-06368 TRANSVERSE MARKING, REMOVE	56.000	LFT
366	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,641.000	LFT
367	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	340.000	LFT
368	808-06716 LINE, REMOVE	1,945.000	LFT
369	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
370	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	29,949.000	LFT
371	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	3,386.000	LFT
372	808-10038 TRANSVERSE MARKINGS MULTI-COMPONENT,	925.000	LFT
373	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	177.000	LFT
374	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	6,200.000	LFT
375	808-10078 LINE, MULTI-COMPONENT, DOTTED, WHITE,	80.000	LFT
376	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	3,742.000	LFT
377	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	260.000	LFT
378	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	97.000	LFT
379	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	12.000	EACH
380	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,107.000	EACH

