

CALL ORDER : 141

CONTRACT ID : R -30431-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-94749 CURB, ASPHALT, REMOVE	1,316.000	LFT
11	207-08263 SUBGRADE TREATMENT, TYPE IA	5,251.000	SYS
12	211-02050 B BORROW	10.000	CYS
13	303-07449 COMPACTED AGGREGATE, NO. 73	3,785.000	TON
14	304-07783 HMA PATCHING, TYPE D	212.000	TON
15	305-09888 RELIEF JOINT	370.000	LFT
16	306-08033 MILLING, ASPHALT, 1 IN	1,098.000	SYS
17	306-08034 MILLING, ASPHALT, 1 1/2 IN	13,799.000	SYS
18	306-08036 MILLING, ASPHALT, 2 IN	213,906.000	SYS
19	306-08043 MILLING, TRANSITION	10,360.000	SYS
20	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
21	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	5,522.000	TON
22	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	10,167.000	TON
23	401-07405 QC/QA-HMA, 5, 76, INTERMEDIATE, 19.0 mm	31,161.000	TON
24	401-10258 JOINT ADHESIVE, SURFACE	234,390.000	LFT
25	401-10259 JOINT ADHESIVE, INTERMEDIATE	165,225.000	LFT
26	406-05520 ASPHALT FOR TACK COAT	156.000	TON
27	410-09086 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm - SMA	13,355.000	TON
28	503-05240 D-1 CONTRACTION JOINT	5,802.000	LFT
29	506-06333 PCCP PATCHING, FULL DEPTH	5,251.000	SYS
30	507-07480 PROFILING PCCP	970.000	SYS
31	507-07482 CRACKS IN PCCP, ROUT AND SEAL	3,600.000	LFT
32	507-07505 RETROFIT LOAD TRANSFER	75.000	EACH
33	507-08272 JOINTS IN PCCP, SAW AND SEAL	37,574.000	LFT
34	601-02241 GUARDRAIL, REMOVE	1,200.000	LFT
35	601-06035 GUARDRAIL, RESET	18,743.000	LFT
36	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
37	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	3,369.000	LFT
38	606-07484 MILLED HMA CORRUGATIONS	67,993.000	LFT
39	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	22.000	TON
40	612-60410 DRILLED HOLE FOR UNDERSEAL	388.000	EACH
41	628-09402 FIELD OFFICE, B	10.000	MOS
42	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	10.000	MOS
43	628-11730 CELLULAR TELEPHONE TYPE B	4.000	EACH
44	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
45	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
46	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	40.000	MOS
47	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	1,794.000	LFT
48	718-03277 PIPE, UNDERDRAIN, CORRUGATED PLASTIC, PERFORATED, 6 IN.	67,993.000	LFT
49	718-06526 HMA FOR UNDERDRAINS	11,219.000	TON

CALL ORDER : 141

CONTRACT ID : R -30431-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	718-06529 OUTLET PROTECTOR, 2	156.000	EACH
51	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	67,993.000	LFT
52	718-52610 AGGREGATE FOR UNDERDRAINS	6,896.000	CYS
53	718-99153 GEOTEXTILES FOR UNDERDRAIN	19,517.000	SYS
54	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
55	801-03290 CONSTRUCTION SIGN, C	16.000	EACH
56	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	68,640.000	LFT
57	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	119,719.000	LFT
58	801-06640 CONSTRUCTION SIGN, A	72.000	EACH
59	801-06710 FLASHING ARROW SIGN	180.000	DAY
60	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
61	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH
62	802-07060 SIGN, SHEET, RELOCATE	5.000	EACH
63	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	67,993.000	LFT
64	808-06716 LINE, REMOVE	109,503.000	LFT
65	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
66	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	2,554.000	LFT
67	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	1,008.000	LFT
68	808-10071 LINE, MULTI-COMPONENT, BROKEN,	255.000	LFT
69	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	67,993.000	LFT
70	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,301.000	EACH
71	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,301.000	EACH
72	808-96075 LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN	18,016.000	LFT

CALL ORDER : 151

CONTRACT ID : R -31058-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION OR REPAIR		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-01502 LIGHT STANDARD, REMOVE	4.000	EACH
12	202-02240 PAVEMENT REMOVAL	1,138.000	SYS
13	202-04997 RAILROAD	LUMP	LUMP
14	202-06541 REMOVE	55.000	EACH
15	202-06541 REMOVE	65.000	EACH
16	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
17	202-51822 BRIDGE DECK OVERLAY, REMOVE	2,491.000	SYS
18	202-93741 GUARDRAIL END TREATMENT, REMOVE	5.000	EACH
19	202-94954 BARRIER WALL, CONCRETE, REMOVE	1,356.000	LFT
20	203-02000 EXCAVATION, COMMON	1,374.000	CYS
21	203-08607 LINEAR GRADING	3,530.000	LFT
22	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	89.000	CYS
23	207-08263 SUBGRADE TREATMENT, TYPE IA	3,209.000	SYS
24	211-06467 AGGREGATE FOR END BENT BACKFILL	91.000	CYS
25	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	6.000	CYS
26	302-06464 SUBBASE FOR PCCP	58.000	CYS
27	302-07455 DENSE GRADED SUBBASE	58.000	CYS
28	303-01180 COMPACTED AGGREGATE, NO. 53	1,500.000	TON
29	304-07783 HMA PATCHING, TYPE D	2,910.000	TON
30	306-08034 MILLING, ASPHALT, 1 1/2 IN	50,900.000	SYS
31	306-08036 MILLING, ASPHALT, 2 IN	189,330.000	SYS
32	306-08043 MILLING, TRANSITION	2,554.000	SYS
33	306-08432 MILLING, APPROACH	6,510.000	SYS
34	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
35	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	4,410.000	TON
36	401-07348 QC/QA-HMA, 4, 70, SURFACE, 12.5 mm	21,870.000	TON
37	401-10258 JOINT ADHESIVE, SURFACE	109,518.000	LFT
38	401-10259 JOINT ADHESIVE, INTERMEDIATE	7,688.000	LFT
39	402-07784 HMA SURFACE, TYPE D	265.000	TON
40	402-07785 HMA INTERMEDIATE, TYPE D	442.000	TON
41	402-07786 HMA BASE, TYPE D	1,412.000	TON
42	406-05520 ASPHALT FOR TACK COAT	65.000	TON
43	406-05521 ASPHALT FOR TACK COAT	8,152.000	SYS
44	502-06329 PCCP, 12 IN	723.000	SYS
45	503-03489 RETROFITTED TIE BARS	276.000	EACH
46	503-05240 D-1 CONTRACTION JOINT	100.000	LFT
47	503-05310 TERMINAL JOINT	163.000	LFT
48	506-06333 PCCP PATCHING, FULL DEPTH	400.000	SYS
49	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH

CALL ORDER : 151

CONTRACT ID : R -31058-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION OR REPAIR		
50	601-02103 GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING	515.000	LFT
51	601-02241 GUARDRAIL, REMOVE	3,310.000	LFT
52	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	2.000	EACH
53	601-94689 GUARDRAIL END TREATMENT, OS	5.000	EACH
54	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	2,595.000	LFT
55	601-99132 GUARDRAIL, TRANSITION, VH, 6 FT-3 IN SPACING	4.000	EACH
56	602-06729 BARRIER DELINEATOR	29.000	EACH
57	602-91266 CONCRETE MEDIAN BARRIER, MODIFIED	1,310.000	LFT
58	606-07484 MILLED HMA CORRUGATIONS	28,090.000	LFT
59	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	415.000	SYS
60	610-07487 HMA FOR APPROACHES, TYPE B	191.000	TON
61	610-07788 HMA FOR APPROACHES, TYPE D	760.000	TON
62	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	24.000	TON
63	612-60410 DRILLED HOLE FOR UNDERSEAL	384.000	EACH
64	616-02320 GEOTEXTILES	216.000	SYS
65	616-93772 INSPECTION HOLE	6.000	EACH
66	619-11050 CLEAN STEEL BRIDGE, PARTIAL, QP-2, BR. NO.	LUMP	LUMP
67	619-51860 PAINT STEEL BRIDGE, PARTIAL, BR. NO.	LUMP	LUMP
68	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
69	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	100.000	SYS
70	621-06559 MULCHED SEEDING, R	100.000	SYS
71	628-09402 FIELD OFFICE, B	10.000	MOS
72	628-11729 CELLULAR TELEPHONE TYPE A	3.000	EACH
73	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
74	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
75	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	30.000	MOS
76	702-51005 CONCRETE, A, SUBSTRUCTURE	19.000	CYS
77	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	1,028.000	LBS
78	702-51863 FIELD DRILLED HOLE IN CONCRETE	751.000	EACH
79	702-93722 CONCRETE, C	150.000	CYS
80	703-06028 REINFORCING BARS	1,710.000	LBS
81	703-06029 REINFORCING BARS, EPOXY COATED	148,377.000	LBS
82	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	655.000	EACH
83	704-51002 CONCRETE, C, SUPERSTRUCTURE	403.000	CYS
84	706-11621 CONCRETE BRIDGE RAILING TRANSITION, TFT	4.000	EACH
85	706-51020 RAILING, CONCRETE, C	149.000	CYS
86	709-51821 SURFACE SEAL	LUMP	LUMP
87	710-09158 PATCHING CONCRETE STRUCTURES	90.000	SFT
88	711-01373 BOLT	16.000	EACH
89	711-51038 STRUCTURAL STEEL	LUMP	LUMP
90	711-51864 DRILLED HOLE	5,092.000	EACH
91	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
92	711-96800 STUD SHEAR CONNECTORS	438.000	EACH
93	715-05407 PIPE, END BENT DRAIN, 6 IN	200.000	LFT
94	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	4,195.000	SFT
95	722-51842 BRIDGE DECK OVERLAY	4,345.000	SYS
96	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	68.000	CYS
97	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	8,390.000	SFT
98	722-60824 SURFACE MILLING	4,345.000	SYS

CALL ORDER : 151

CONTRACT ID : R -31058-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION OR REPAIR		
99	724-51925 STRUCTURAL EXPANSION JOINT, SS	182.000	LFT
100	726-92406 BEARING ASSEMBLY, ELASTOMERIC	65.000	EACH
101	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
102	801-03290 CONSTRUCTION SIGN, C	11.000	EACH
103	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
104	801-06201 TEMPORARY PANEL SIGNS	482.000	SFT
105	801-06202 TEMPORARY PANEL SIGN SUPPORTS	390.000	LFT
106	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	18,250.000	LFT
107	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	45,168.000	LFT
108	801-06625 DETOUR ROUTE MARKER ASSEMBLY	30.000	EACH
109	801-06640 CONSTRUCTION SIGN, A	86.000	EACH
110	801-06645 CONSTRUCTION SIGN, B	18.000	EACH
111	801-06710 FLASHING ARROW SIGN	800.000	DAY
112	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
113	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	1.000	EACH
114	801-07118 BARRICADE, III-A	164.000	LFT
115	801-08507 TEMPORARY TRAFFIC BARRIER, TYPE 1, ANCHORED	2,870.000	LFT
116	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	880.000	LFT
117	801-11598 ARIES FIELD PROCESSOR FOR PCMS	1.000	EACH
118	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	4.000	EACH
119	802-02475 SIGN, PANEL, RELOCATE	2.000	EACH
120	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	2,970.000	LFT
121	805-78785 SIGNAL DETECTOR HOUSING	8.000	EACH
122	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,320.000	LFT
123	807-02822 LIGHT POLE, STEEL, RELOCATE	4.000	EACH
124	808-06368 TRANSVERSE MARKING, REMOVE	80.000	LFT
125	808-06716 LINE, REMOVE	39,976.000	LFT
126	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
127	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	4,320.000	LFT
128	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	73,250.000	LFT
129	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	73,068.000	LFT
130	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	7,385.000	LFT
131	808-10038 TRANSVERSE MARKINGS MULTI-COMPONENT,	945.000	LFT
132	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	200.000	LFT
133	808-10052 PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, (ONLY)	1.000	EACH
134	808-10053 PAVEMENT MESSAGE MARKING, MULTI-COMPONENT,	6.000	EACH
135	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	11,350.000	LFT
136	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	2.000	EACH
137	808-75510 TRANSVERSE MARKINGS, PREFORMED PLASTIC,	80.000	LFT
138	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	904.000	EACH
139	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	904.000	EACH
140	808-95638 CENTER CURB PAINTING	840.000	SFT

CALL ORDER : 171

CONTRACT ID : R -31776-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	113-01614 PARTNERING OVERHEAD	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
14	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
15	203-02000 EXCAVATION, COMMON	21,778.000	CYS
16	203-02020 EXCAVATION, UNCLASSIFIED	500.000	CYS
17	203-51223 EXCAVATION, WATERWAY	2,168.000	CYS
18	205-03371 SEDIMENT, REMOVE	500.000	CYS
19	205-06933 TEMPORARY INLET PROTECTION	1.000	EACH
20	205-06936 TEMPORARY SEDIMENT TRAP	200.000	TON
21	205-06937 TEMPORARY SILT FENCE	1,882.000	LFT
22	205-09543 NO 2 STONE	100.000	TON
23	205-11584 TEMPORARY CHECK DAM, TRAVERSABLE	1,936.000	LFT
24	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	32.000	CYS
25	207-08265 SUBGRADE TREATMENT, TYPE IIA	31,038.000	SYS
26	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,948.000	SYS
27	211-02050 B BORROW	2,449.000	CYS
28	211-06467 AGGREGATE FOR END BENT BACKFILL	19.000	CYS
29	211-09264 STRUCTURAL BACKFILL, TYPE 1	155.000	CYS
30	211-09265 STRUCTURAL BACKFILL, TYPE 2	293.000	CYS
31	211-09267 STRUCTURAL BACKFILL, TYPE 4	14.000	CYS
32	211-09268 STRUCTURAL BACKFILL, TYPE 5	143.000	CYS
33	302-07455 DENSE GRADED SUBBASE	83.000	CYS
34	303-01180 COMPACTED AGGREGATE, NO. 53	10,587.000	TON
35	303-07449 COMPACTED AGGREGATE, NO. 73	103.000	TON
36	304-07493 WIDENING WITH HMA, TYPE B	955.000	TON
37	306-08034 MILLING, ASPHALT, 1 1/2 IN	149.000	SYS
38	306-08042 MILLING, SCARIFICATION/PROFILE	6,495.000	SYS
39	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
40	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2,378.000	TON
41	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	4,168.000	TON
42	401-10258 JOINT ADHESIVE, SURFACE	21,767.000	LFT
43	401-10259 JOINT ADHESIVE, INTERMEDIATE	21,767.000	LFT
44	401-11785 LIQUID ASPHALT SEALANT	21,767.000	LFT
45	406-05520 ASPHALT FOR TACK COAT	12.000	TON
46	601-01128 GUARDRAIL, TRANSITION TYPE WGB	7.000	EACH
47	601-01128 GUARDRAIL, TRANSITION TYPE WGB	1.000	EACH
48	601-01626 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 2	1.000	EACH
49	601-01704 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, MODIFIED	1.000	EACH

CALL ORDER : 171

CONTRACT ID : R -31776-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	601-01740 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 4	1.000	EACH
51	601-01839 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 6	2.000	EACH
52	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
53	601-01848 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 5	2.000	EACH
54	601-02103 GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING	157.000	LFT
55	601-02241 GUARDRAIL, REMOVE	261.000	LFT
56	601-05071 GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, 7	1.000	EACH
57	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
58	601-94689 GUARDRAIL END TREATMENT, OS	16.000	EACH
59	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,644.000	LFT
60	605-06145 CURB AND GUTTER, B, CONCRETE	271.000	LFT
61	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	516.000	SYS
62	610-07486 HMA FOR APPROACHES, TYPE A	236.000	TON
63	610-07487 HMA FOR APPROACHES, TYPE B	922.000	TON
64	610-08446 PCCP FOR APPROACHES, 6 IN	48.000	SYS
65	611-06497 MAILBOX ASSEMBLY, SINGLE	18.000	EACH
66	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
67	615-06505 MONUMENT, B	11.000	EACH
68	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
69	616-02320 GEOTEXTILES	2,645.000	SYS
70	616-05688 RIPRAP, CLASS 1	184.000	TON
71	616-06405 RIPRAP, REVETMENT	1,231.000	TON
72	616-06451 RIPRAP, UNIFORM	334.000	TON
73	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
74	621-06545 FERTILIZER	4.000	TON
75	621-06554 SEED MIXTURE, U	1,588.000	LBS
76	621-06557 SEED MIXTURE, T	1,401.000	LBS
77	621-06565 MULCHING MATERIAL	37.000	TON
78	621-06567 WATER	45.900	KGAL
79	621-06574 SODDING	5,039.000	SYS
80	621-06575 SODDING, NURSERY	7,703.000	SYS
81	628-09402 FIELD OFFICE, B	24.000	MOS
82	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	24.000	MOS
83	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
84	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
85	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
86	628-11780 CELLULAR TELEPHONE SERVICE, 500 MINUTES	48.000	MOS
87	701-09558 TEST PILE, INDICATOR, PRODUCTION	514.000	LFT
88	701-09560 TEST PILE, INDICATOR, RESTRIKE	8.000	EACH
89	701-09739 PILE SHOE, HP 12 X 53	32.000	EACH
90	701-51195 PILE, STEEL H, HP 12 IN X 53	1,336.000	LFT
91	701-97874 PILE, STEEL H, REINFORCED CONCRETE ENCASED, HP 12 IN X 53	220.000	LFT
92	702-51005 CONCRETE, A, SUBSTRUCTURE	30.600	CYS
93	702-51863 FIELD DRILLED HOLE IN CONCRETE	48.000	EACH
94	702-90915 CONCRETE, CLASS A	4.000	CYS
95	703-06028 REINFORCING BARS	15,692.000	LBS
96	703-06029 REINFORCING BARS, EPOXY COATED	61,598.000	LBS
97	704-51006 CONCRETE, C, SUPERSTRUCTURE, MODIFIED	255.200	CYS
98	706-04683 RAILING,	24.000	LFT

CALL ORDER : 171

CONTRACT ID : R -31776-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
99	706-06352 CONCRETE BRIDGE RAILING TRANSITION, TPF-2	8.000	EACH
100	706-09963 RAILING, CONCRETE, PF-2	214.100	LFT
101	706-11405 RAILING, STEEL, PF-2	248.500	LFT
102	707-09029 STRUCTURAL MEMBER, CONCRETE BOX BEAM, 12 IN X 48 IN	676.000	LFT
103	707-10179 STRUCTURAL MEMBER, CONCRETE BOX	169.000	LFT
104	708-51813 PNEUMATICALLY PLACED MORTAR	50.000	SFT
105	709-51821 SURFACE SEAL	LUMP	LUMP
106	709-51821 SURFACE SEAL	LUMP	LUMP
107	710-51870 REPOINTING MASONRY IN STRUCTURES	20.000	SFT
108	714-11113 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	74.000	LFT
109	714-11170 STRUCTURE EXTENSION REINFORCED CONCRETE BOX SECTIONS,	29.000	LFT
110	714-11173 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	80.000	LFT
111	714-11198 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	68.000	LFT
112	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	207.000	LFT
113	715-05049 PIPE, TYPE 4 CIRCULAR 8 IN	200.000	LFT
114	715-05051 PIPE, TYPE 4 CIRCULAR 10 IN	200.000	LFT
115	715-05052 PIPE, TYPE 4 CIRCULAR 12 IN	200.000	LFT
116	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	85.000	LFT
117	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	86.000	LFT
118	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	76.000	LFT
119	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	129.000	LFT
120	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	641.000	LFT
121	715-05173 PIPE, TYPE 3 CIRCULAR 24 IN	141.000	LFT
122	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	210.000	LFT
123	715-05208 PIPE, TYPE 4 CIRCULAR 15 IN	1,369.000	LFT
124	715-05407 PIPE, END BENT DRAIN, 6 IN	104.000	LFT
125	715-05596 PIPE EXTENSION, CIRCULAR 18 IN	24.000	LFT
126	715-06471 PIPE END SECTION, MIN AREA 3.3 SFT	4.000	EACH
127	715-08243 PIPE, TYPE 3 DEFORMED MIN AREA 3.3 SFT	64.000	LFT
128	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	25.000	TON
129	715-09064 VIDEO INSPECTION FOR PIPE	562.000	LFT
130	715-46005 PIPE END SECTION, DIA 15"	32.000	EACH
131	715-46010 PIPE END SECTION, DIA 18"	1.000	EACH
132	715-46020 PIPE END SECTION, DIA 24"	12.000	EACH
133	718-52610 AGGREGATE FOR UNDERDRAINS	134.000	CYS
134	718-99153 GEOTEXTILES FOR UNDERDRAIN	1,638.000	SYS
135	719-09392 PIPE, DRAIN TILE TERMINAL SECTION, 15 IN	10.000	LFT
136	720-08299 INLET, DROP	1.000	EACH
137	720-44000 CASTING, ADJUST TO GRADE	8.000	EACH
138	720-45035 INLET, F7	4.000	EACH
139	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	9.000	LFT
140	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	82.000	LFT
141	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
142	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
143	801-06625 DETOUR ROUTE MARKER ASSEMBLY	20.000	EACH
144	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
145	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
146	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
147	801-07118 BARRICADE, III-A	188.000	LFT



CALL ORDER : 171

CONTRACT ID : R -31776-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
148	801-07119 BARRICADE, III-B	96.000	LFT
149	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	193.000	LFT
150	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	53.000	SFT
151	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	9.000	SFT
152	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	16.000	SFT
153	802-09841 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.125 IN THICKNESS	81.000	SFT
154	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	14,631.000	LFT
155	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	534.000	LFT
156	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	630.000	LFT
157	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	1.000	EACH
158	808-10119 TRANSVERSE MARKING, MULTI-COMPONENT,	7.000	LFT
159	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	13,311.000	LFT
160	808-75290 TRANSVERSE MARKING, THERMOPLASTIC,	90.000	LFT
161	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	238.000	LFT
162	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH
163	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	192.000	EACH

CALL ORDER : 191

CONTRACT ID : R -33922-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PIPE LINING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	601-06035 GUARDRAIL, RESET	200.000	LFT
8	616-02320 GEOTEXTILES	220.000	SYS
9	616-05688 RIPRAP, CLASS 1	173.000	TON
10	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
11	621-03787 SEED MIXTURE, D	30.000	LBS
12	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
13	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
14	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
15	628-11780 CELLULAR TELEPHONE SERVICE, 500 MINUTES	8.000	MOS
16	725-10245 PERPETUATION, EXISTING PIPE	1.000	EACH
17	725-11288 PIPE LINER, CURED-IN-PLACE, 60"	140.000	LFT
18	725-11399 PIPE LINER, CURED-IN-PLACE, 84 IN	224.000	LFT
19	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
20	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
21	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
22	801-06710 FLASHING ARROW SIGN	20.000	DAY
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
24	804-06771 DELINEATOR POST, FLEXIBLE	4.000	EACH

CALL ORDER : 201

CONTRACT ID : R -33928-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SMALL STRUCTURE REPLACEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	207-09935 SUBGRADE TREATMENT, TYPE 1C	74.000	SYS
9	211-09264 STRUCTURAL BACKFILL, TYPE 1	517.000	CYS
10	303-01180 COMPACTED AGGREGATE, NO. 53	9.000	TON
11	402-07434 HMA SURFACE, TYPE C	6.500	TON
12	402-07439 HMA INTERMEDIATE, TYPE C	10.500	TON
13	402-07442 HMA BASE, TYPE C	24.500	TON
14	406-05520 ASPHALT FOR TACK COAT	0.100	TON
15	616-05688 RIPRAP, CLASS 1	180.000	TON
16	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
17	621-03787 SEED MIXTURE, D	0.500	LBS
18	628-09402 FIELD OFFICE, B	3.000	MOS
19	715-07625 PIPE, TYPE 1 CIRCULAR MIN AREA 66 IN	59.000	LFT
20	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
21	801-04308 ROAD CLOSURE SIGN ASSEMBLY	10.000	EACH
22	801-06625 DETOUR ROUTE MARKER ASSEMBLY	13.000	EACH
23	801-06640 CONSTRUCTION SIGN, A	35.000	EACH
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
25	801-07119 BARRICADE, III-B	168.000	LFT
26	804-06771 DELINEATOR POST, FLEXIBLE	2.000	EACH
27	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	44.000	LFT
28	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	44.000	LFT
29	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.000	EACH
30	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	2.000	EACH

CALL ORDER : 211

CONTRACT ID : R -34178-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE PIPE LINING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	725-11300 PIPE LINER, CURED-IN-PLACE, 8.9 SFT	205.000	LFT
8	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
9	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
10	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 221

CONTRACT ID : R -34184-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE PIPE LINING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-96133 PIPE, REMOVE	2.000	LFT
8	203-02000 EXCAVATION, COMMON	18.000	CYS
9	616-02320 GEOTEXTILES	28.900	SYS
10	616-05689 RIPRAP, CLASS 2	22.900	TON
11	702-90915 CONCRETE, CLASS A	4.600	CYS
12	703-06029 REINFORCING BARS, EPOXY COATED	135.000	LBS
13	709-51821 SURFACE SEAL	LUMP	LUMP
14	715-06566 PIPE EXTENSION, CIRCULAR, 6"	6.000	LFT
15	715-11746 PIPE, TYPE 1 DEFORMED MIN AREA 14.2 SFT	2.000	LFT
16	725-11709 PIPE LINER, CURED-IN-PLACE, 12.5 SFT	91.000	LFT
17	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
18	801-06640 CONSTRUCTION SIGN, A	2.000	EACH
19	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 231

CONTRACT ID : R -34197-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02278 CURB, CONCRETE, REMOVE	219.000	LFT
11	205-03371 SEDIMENT, REMOVE	100.000	CYS
12	205-06932 TEMPORARY CHECK DAM, STRAW BALES	378.000	LFT
13	205-06933 TEMPORARY INLET PROTECTION	3.000	EACH
14	205-06937 TEMPORARY SILT FENCE	102.000	LFT
15	207-09934 SUBGRADE TREATMENT, TYPE 1B	14,887.000	SYS
16	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,070.000	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,097.000	TON
18	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	984.000	TON
19	306-08034 MILLING, ASPHALT, 1 1/2 IN	524.000	SYS
20	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	313.000	TON
21	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	275.000	TON
22	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	21.000	TON
23	406-05520 ASPHALT FOR TACK COAT	2.000	TON
24	604-07901 CURB RAMP, CONCRETE, G	65.000	SYS
25	605-06140 CURB AND GUTTER, CONCRETE	3,011.000	LFT
26	615-06490 RIGHT OF WAY MARKER	17.000	EACH
27	615-06505 MONUMENT, B	4.000	EACH
28	616-02320 GEOTEXTILES	81.000	SYS
29	616-06405 RIPRAP, REVETMENT	53.000	TON
30	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
31	621-02770 EROSION CONTROL BLANKET	340.000	SYS
32	621-06545 FERTILIZER	1.100	TON
33	621-06554 SEED MIXTURE, U	267.000	LBS
34	621-06557 SEED MIXTURE, T	534.000	LBS
35	621-06565 MULCHING MATERIAL	11.000	TON
36	628-09403 FIELD OFFICE, C	12.000	MOS
37	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
38	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
39	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
40	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	24.000	MOS
41	715-01471 PIPE END SECTION, PRECAST CONCRETE, 15 IN	2.000	EACH
42	715-01765 PIPE END SECTION, PRECAST CONCRETE, 12 IN	1.000	EACH
43	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	6,185.000	LFT
44	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	634.000	LFT
45	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	703.000	LFT
46	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	356.000	LFT
47	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	1,091.000	LFT
48	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	144.000	LFT
49	715-08048 STORMWATER TREATMENT SYSTEM	1.000	EACH

CALL ORDER : 231

CONTRACT ID : R -34197-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
50	715-09064 VIDEO INSPECTION FOR PIPE	2,928.000	LFT
51	715-46030 PIPE END SECTION, DIA 30"	1.000	EACH
52	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
53	718-52610 AGGREGATE FOR UNDERDRAINS	489.000	CYS
54	718-99153 GEOTEXTILES FOR UNDERDRAIN	5,304.000	SYS
55	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
56	720-45030 INLET, E7	2.000	EACH
57	720-45410 MANHOLE, C4	16.000	EACH
58	720-45415 MANHOLE, D4	2.000	EACH
59	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	2.000	LFT
60	720-98174 INLET, B15	15.000	EACH
61	720-98555 INLET, C15	5.000	EACH
62	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	3.000	EACH
63	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
64	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	1,622.000	LFT
65	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	23.000	LFT
66	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
67	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
68	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
69	801-07118 BARRICADE, III-A	204.000	LFT
70	801-07119 BARRICADE, III-B	48.000	LFT
71	802-04089 SIGN, SHEET, REMOVE	1.000	EACH
72	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	250.000	LFT
73	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	127.250	SFT
74	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	15.000	SFT
75	808-05929 TRANSVERSE MARKING THERMOPLASTIC,	89.000	LFT
76	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,804.000	LFT
77	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,007.000	LFT
78	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	5,654.000	LFT
79	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	129.000	LFT
80	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	11.000	EACH
81	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	10.000	EACH
SECTION NO. 0002 NEW ROAD CONSTRUCTION			
82	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
83	203-02000 EXCAVATION, COMMON	8,365.000	CYS
84	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	373.000	TON
85	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,075.000	TON
86	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,791.000	TON
87	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	2,055.000	TON
88	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	2,060.000	TON
89	406-05520 ASPHALT FOR TACK COAT	13.000	TON
SECTION NO. 0003 NEW ROAD CONSTRUCTION			
90	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
91	203-02000 EXCAVATION, COMMON	10,569.000	CYS
92	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	249.000	TON

CALL ORDER : 231

CONTRACT ID : R -34197-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	NEW ROAD CONSTRUCTION		
93	302-06464 SUBBASE FOR PCCP	3,333.000	CYS
94	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	94.000	TON
95	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	187.000	TON
96	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	187.000	TON
97	406-05520 ASPHALT FOR TACK COAT	1.000	TON
98	501-11663 QC/QA-PCCP, 7.5 IN	11,956.000	SYS



CALL ORDER : 241

CONTRACT ID : R -34338-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	469.000	SYS
12	202-02278 CURB, CONCRETE, REMOVE	7,185.000	LFT
13	202-02928 CATCH BASIN, REMOVE	37.000	EACH
14	202-52710 SIDEWALK, CONCRETE, REMOVE	4,674.000	SYS
15	202-91840 FENCE, CHAIN LINK, REMOVE	53.000	LFT
16	202-93047 MANHOLE, REMOVE	16.000	EACH
17	202-96133 PIPE, REMOVE	11,107.000	LFT
18	203-02000 EXCAVATION, COMMON	7,675.000	CYS
19	203-02070 BORROW	630.000	CYS
20	205-06933 TEMPORARY INLET PROTECTION	93.000	EACH
21	205-09543 NO 2 STONE	300.000	TON
22	205-11587 TEMPORARY GEOTEXTILE	705.000	SYS
23	207-08263 SUBGRADE TREATMENT, TYPE IA	16,727.000	SYS
24	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,004.000	SYS
25	211-09264 STRUCTURAL BACKFILL, TYPE 1	5,327.000	CYS
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,196.000	TON
27	304-07490 HMA PATCHING, TYPE B	4.000	TON
28	304-07493 WIDENING WITH HMA, TYPE B	7.000	TON
29	306-08034 MILLING, ASPHALT, 1 1/2 IN	81.000	SYS
30	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	903.000	TON
31	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	2,089.000	TON
32	401-10258 JOINT ADHESIVE, SURFACE	12,091.000	LFT
33	401-10259 JOINT ADHESIVE, INTERMEDIATE	12,091.000	LFT
34	406-05520 ASPHALT FOR TACK COAT	3.100	TON
35	603-06045 FENCE, CHAIN LINK, 48 IN	52.000	LFT
36	604-06070 SIDEWALK, CONCRETE	5,479.000	SYS
37	604-07897 CURB RAMP, CONCRETE, C	123.000	SYS
38	604-07900 CURB RAMP, CONCRETE, F	60.000	SYS
39	604-07901 CURB RAMP, CONCRETE, G	8.000	SYS
40	604-07902 CURB RAMP, CONCRETE, H	330.000	SYS
41	604-07904 CURB RAMP, CONCRETE, L	15.000	SYS
42	605-52807 CURB AND GUTTER, COMBINED	7,409.000	LFT
43	610-07487 HMA FOR APPROACHES, TYPE B	238.000	TON
44	610-08446 PCCP FOR APPROACHES, 6 IN	557.000	SYS
45	610-09108 PCCP FOR APPROACHES, 9 IN	410.000	SYS
46	615-06505 MONUMENT, B	7.000	EACH
47	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
48	621-06567 WATER	6.000	KGAL
49	621-06570 TOPSOIL	165.000	CYS

CALL ORDER : 241

CONTRACT ID : R -34338-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT		
50	621-06575 SODDING, NURSERY	1,447.000	SYS
51	621-90853 TAPPING SLEEVE WITH VALVE	1.000	EACH
52	628-09403 FIELD OFFICE, C	22.000	MOS
53	715-02433 VALVE WITH BOX, RESTRAINED GATE DUCTILE IRON, 12 IN	16.000	EACH
54	715-02743 GATE VALVE WITH VALVE BOX 4 IN	4.000	EACH
55	715-03053 METER PIT	1.000	EACH
56	715-04750 CORPORATION STOP	106.000	EACH
57	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,649.000	LFT
58	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	375.000	LFT
59	715-05408 PIPE SANITARY SEWER 8 IN	112.000	LFT
60	715-05409 PIPE SANITARY SEWER 10 IN	48.000	LFT
61	715-05411 PIPE SANITARY SEWER 12 IN	1,567.000	LFT
62	715-05412 PIPE SANITARY SEWER 15 IN	1,210.000	LFT
63	715-05413 PIPE SANITARY SEWER 18 IN	434.000	LFT
64	715-05711 PIPE SANITARY SEWER 6 IN	2,080.000	LFT
65	715-07794 WATER MAIN CONNECTIONS	13.000	EACH
66	715-09064 VIDEO INSPECTION FOR PIPE	2,024.000	LFT
67	715-94780 WATER MAIN, DUCTILE IRON, 6 IN	40.000	LFT
68	715-96629 WATER SERVICE LINE, 1 IN	2,985.000	LFT
69	715-96670 WATER MAIN, DUCTILE IRON, 12 IN	3,617.000	LFT
70	715-98265 WATER MAIN, DUCTILE IRON, 4 IN	60.000	LFT
71	719-93923 DUCTILE IRON FITTINGS	10,580.000	LBS
72	720-04682 INLET	32.000	EACH
73	720-44000 CASTING, ADJUST TO GRADE	6.000	EACH
74	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	1.000	EACH
75	720-45410 MANHOLE, C4	14.000	EACH
76	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	17.000	LFT
77	720-93501 MANHOLE, L4	3.000	EACH
78	720-95335 MANHOLE, M4	6.000	EACH
79	720-95422 MANHOLE, J4	1.000	EACH
80	720-96999 FIRE HYDRANT ASSEMBLY	8.000	EACH
81	720-97009 FIRE HYDRANT ASSEMBLY, REMOVE	9.000	EACH
82	720-98363 CATCH BASIN, MODIFIED	26.000	EACH
83	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
84	801-04308 ROAD CLOSURE SIGN ASSEMBLY	17.000	EACH
85	801-06625 DETOUR ROUTE MARKER ASSEMBLY	7.000	EACH
86	801-06640 CONSTRUCTION SIGN, A	1.000	EACH
87	801-06645 CONSTRUCTION SIGN, B	15.000	EACH
88	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
89	801-07118 BARRICADE, III-A	324.000	LFT
90	801-07119 BARRICADE, III-B	288.000	LFT
91	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	713.000	LFT
92	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	37.000	EACH
93	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	250.000	SFT
94	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	54.000	SFT
95	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	135.000	SFT
96	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	7,662.000	LFT
97	807-02191 HANDHOLE, LIGHTING	2.000	EACH
98	807-03758 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING	82.000	EACH

CALL ORDER : 241

CONTRACT ID : R -34338-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT		
99	807-03934 LIGHT STRUCTURE, REMOVE	9.000	EACH
100	807-03950 LUMINAIRE, ORNAMENTAL	78.000	EACH
101	807-03950 LUMINAIRE, ORNAMENTAL	4.000	EACH
102	807-03951 LIGHT POLE, ORNAMENTAL	82.000	EACH
103	807-86810 SERVICE POINT, II	2.000	EACH
104	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	2,296.000	LFT
105	807-86910 CONNECTOR KIT, UNFUSED	82.000	EACH
106	807-86915 CONNECTOR KIT, FUSED	82.000	EACH
107	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	222.000	EACH
108	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.000	EACH
109	807-86930 INSULATION LINK, NON-WATERPROOFED	172.000	EACH
110	807-86935 INSULATION LINK, WATERPROOFED	8.000	EACH
111	807-97237 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	8,502.000	LFT
112	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,285.000	LFT
113	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	236.000	LFT
114	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	1,447.000	LFT
115	808-75340 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH
116	808-97664 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	14.000	EACH

CALL ORDER : 251

CONTRACT ID : R -35188-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SAFE ROUTE TO SCHOOL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	879.000	SYS
11	203-08607 LINEAR GRADING	1,500.000	LFT
12	205-06933 TEMPORARY INLET PROTECTION	14.000	EACH
13	205-06937 TEMPORARY SILT FENCE	200.000	LFT
14	207-08267 SUBGRADE TREATMENT, TYPE IIIA	403.000	SYS
15	211-09264 STRUCTURAL BACKFILL, TYPE 1	11.000	CYS
16	303-07449 COMPACTED AGGREGATE, NO. 73	11.000	TON
17	304-07490 HMA PATCHING, TYPE B	12.000	TON
18	502-06627 PCCP, 6 IN	134.000	SYS
19	604-06070 SIDEWALK, CONCRETE	1,205.000	SYS
20	604-06070 SIDEWALK, CONCRETE	56.000	SYS
21	604-07894 CURB RAMP, CONCRETE, A	15.000	SYS
22	604-07897 CURB RAMP, CONCRETE, C	56.000	SYS
23	604-07901 CURB RAMP, CONCRETE, G	67.000	SYS
24	604-07903 CURB RAMP, CONCRETE, K	16.000	SYS
25	605-06120 CURB, CONCRETE	148.000	LFT
26	605-52807 CURB AND GUTTER, COMBINED	10.000	LFT
27	605-92578 CURB WALK, CONCRETE	288.000	SYS
28	610-07487 HMA FOR APPROACHES, TYPE B	16.000	TON
29	610-08446 PCCP FOR APPROACHES, 6 IN	291.000	SYS
30	615-11537 PARKING BARRIER, CONCRETE	7.000	EACH
31	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
32	621-06560 MULCHED SEEDING, U	2,750.000	SYS
33	621-06570 TOPSOIL	230.000	CYS
34	628-09401 FIELD OFFICE, A	6.000	MOS
35	628-11730 CELLULAR TELEPHONE TYPE B	2.000	EACH
36	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
37	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
38	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	12.000	MOS
39	715-05148 PIPE, TYPE 2 CIRCULAR 10 IN	26.000	LFT
40	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	15.000	LFT
41	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	1.000	EACH
42	720-07309 TRENCH DRAIN	24.000	LFT
43	720-07309 TRENCH DRAIN	6.000	LFT
44	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
45	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
46	720-45015 INLET, A8	2.000	EACH
47	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
48	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
49	801-06640 CONSTRUCTION SIGN, A	22.000	EACH

CALL ORDER : 251

CONTRACT ID : R -35188-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SAFE ROUTE TO SCHOOL		
50 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
51 801-07119	BARRICADE, III-B	48.000	LFT

CALL ORDER : 261

CONTRACT ID : R -35223-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SAFE ROUTE TO SCHOOL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	57.000	CYS
10	203-02070 BORROW	1,200.000	CYS
11	205-06937 TEMPORARY SILT FENCE	3,490.000	LFT
12	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,326.000	SYS
13	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	288.000	TON
14	604-06070 SIDEWALK, CONCRETE	1,120.000	SYS
15	604-11738 DETECTABLE WARNING ELEMENT	8.000	LFT
16	610-08446 PCCP FOR APPROACHES, 6 IN	206.000	SYS
17	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	3.000	EACH
18	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
19	621-01852 MULCHED SEEDING, GRASS, 2	1,964.000	SYS
20	628-09402 FIELD OFFICE, B	8.000	MOS
21	715-05115 PIPE, TYPE 1 CIRCULAR 6 IN	37.000	LFT
22	715-05118 PIPE, TYPE 1 CIRCULAR 12 IN	57.000	LFT
23	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	2.000	LFT
24	715-11665 PIPE END SECTION DIA 6"	4.000	EACH
25	715-46000 PIPE END SECTION, DIA 12"	6.000	EACH
26	715-46005 PIPE END SECTION, DIA 15"	1.000	EACH
27	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
28	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
29	801-06640 CONSTRUCTION SIGN, A	19.000	EACH
30	808-74815 TRANSVERSE MARKING, THERMOPLASTIC,	54.000	LFT
31	808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN	40.000	LFT

CALL ORDER : 271

CONTRACT ID : R -35604-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT, ROUNDABOUT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	14,006.000	SYS
12	202-06542 RELOCATE	1.000	EACH
13	202-96133 PIPE, REMOVE	1,615.000	LFT
14	202-96133 PIPE, REMOVE	1,831.000	LFT
15	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
16	203-02000 EXCAVATION, COMMON	1,525.000	CYS
17	203-02070 BORROW	1,530.000	CYS
18	205-06933 TEMPORARY INLET PROTECTION	6.000	EACH
19	205-06937 TEMPORARY SILT FENCE	4,330.000	LFT
20	205-09543 NO 2 STONE	100.000	TON
21	207-08263 SUBGRADE TREATMENT, TYPE IA	13,131.000	SYS
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	322.000	SYS
23	211-09264 STRUCTURAL BACKFILL, TYPE 1	4,631.000	CYS
24	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	990.000	TON
25	302-06464 SUBBASE FOR PCCP	2,249.000	CYS
26	302-06464 SUBBASE FOR PCCP	185.000	CYS
27	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	100.000	TON
28	304-07491 HMA PATCHING, TYPE C	146.000	TON
29	306-08043 MILLING, TRANSITION	902.000	SYS
30	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	237.000	TON
31	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	271.000	TON
32	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	312.000	TON
33	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	315.000	TON
34	401-10258 JOINT ADHESIVE, SURFACE	912.000	LFT
35	401-10259 JOINT ADHESIVE, INTERMEDIATE	912.000	LFT
36	406-05520 ASPHALT FOR TACK COAT	2.000	TON
37	501-09749 QC/QA PCCP, 9.5"	7,215.000	SYS
38	502-09531 PCCP	537.000	SYS
39	503-03489 RETROFITTED TIE BARS	48.000	EACH
40	503-05240 D-1 CONTRACTION JOINT	6,540.000	LFT
41	503-05310 TERMINAL JOINT	198.000	LFT
42	604-04740 PAVERS	576.000	SFT
43	604-04740 PAVERS	1,049.000	SFT
44	604-04740 PAVERS	6,500.000	SFT
45	604-06070 SIDEWALK, CONCRETE	2,567.000	SYS
46	604-06070 SIDEWALK, CONCRETE	34.000	SYS
47	604-07894 CURB RAMP, CONCRETE, A	11.000	SYS
48	604-07897 CURB RAMP, CONCRETE, C	58.000	SYS
49	604-07901 CURB RAMP, CONCRETE, G	15.000	SYS

CALL ORDER : 271

CONTRACT ID : R -35604-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT, ROUNDABOUT		
50	604-07904 CURB RAMP, CONCRETE, L	185.000	SYS
51	605-06120 CURB, CONCRETE	1,245.000	LFT
52	605-06125 CURB, CONCRETE, MODIFIED	579.000	LFT
53	605-06125 CURB, CONCRETE, MODIFIED	143.000	LFT
54	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	66.000	LFT
55	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	767.000	LFT
56	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	3,722.000	LFT
57	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	641.000	LFT
58	605-06215 CENTER CURB, D, CONCRETE	79.000	LFT
59	605-06235 CENTER CURB, D, CONCRETE, MODIFIED	10.000	LFT
60	610-07488 HMA FOR APPROACHES, TYPE C	450.000	TON
61	610-08446 PCCP FOR APPROACHES, 6 IN	23.000	SYS
62	610-09108 PCCP FOR APPROACHES, 9 IN	322.000	SYS
63	611-06497 MAILBOX ASSEMBLY, SINGLE	4.000	EACH
64	614-06470 HEADER, CEMENT CONCRETE, A	217.000	LFT
65	615-06505 MONUMENT, B	2.000	EACH
66	615-06510 MONUMENT, C	2.000	EACH
67	615-06515 MONUMENT, D	4.000	EACH
68	616-02320 GEOTEXTILES	339.000	SYS
69	616-05688 RIPRAP, CLASS 1	55.000	TON
70	618-03812 BENCH	6.000	EACH
71	618-03812 BENCH	1.000	EACH
72	618-97672 TRASH RECEPTACLE	6.000	EACH
73	618-97672 TRASH RECEPTACLE	1.000	EACH
74	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
75	621-06545 FERTILIZER	1.000	TON
76	621-06554 SEED MIXTURE, U	249.000	LBS
77	621-06557 SEED MIXTURE, T	498.000	LBS
78	621-06565 MULCHING MATERIAL	8.000	TON
79	621-06567 WATER	19.000	KGAL
80	621-06570 TOPSOIL	2,220.000	CYS
81	621-06574 SODDING	5,277.000	SYS
82	621-07657 FIBER MAT, COCONUT	3,688.000	SYS
83	621-98038 MULCH, HARDWOOD SHREDDED BARK	25.000	CYS
84	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	17.000	EACH
85	622-05654 PLANT, PERENNIAL	1,142.000	EACH
86	622-07764 IRRIGATION SYSTEM	LUMP	LUMP
87	628-09402 FIELD OFFICE, B	15.000	MOS
88	715-02433 VALVE WITH BOX, RESTRAINED GATE DUCTILE IRON, 12 IN	1.000	EACH
89	715-02529 VALVE WITH BOX, RESTRAINED, BUTTERFLY, DUCTILE	5.000	EACH
90	715-02531 VALVE WITH BOX, RESTRAINED GATE, DUCTILE IRON 6 IN	1.000	EACH
91	715-03025 SANITARY MANHOLE	1.000	EACH
92	715-03025 SANITARY MANHOLE	1.000	EACH
93	715-03025 SANITARY MANHOLE	10.000	EACH
94	715-04596 WATER SERVICE	1.000	EACH
95	715-04596 WATER SERVICE	1.000	EACH
96	715-04612 PIPE	1,134.000	LFT
97	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	88.000	LFT
98	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	2,392.000	LFT



CALL ORDER : 271

CONTRACT ID : R -35604-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT, ROUNDABOUT		
99	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	928.000	LFT
100	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	219.000	LFT
101	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	105.000	LFT
102	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	193.000	LFT
103	715-05159 PIPE, TYPE 2 CIRCULAR 42 IN	137.000	LFT
104	715-05161 PIPE, TYPE 2 CIRCULAR 48 IN	63.000	LFT
105	715-05162 PIPE, TYPE 2 CIRCULAR 54 IN	426.000	LFT
106	715-05163 PIPE, TYPE 2 CIRCULAR 60 IN	1,713.000	LFT
107	715-05409 PIPE SANITARY SEWER 10 IN	96.000	LFT
108	715-05415 PIPE SANITARY SEWER 24 IN	16.000	LFT
109	715-05841 CONCRETE ANCHOR 60 IN	1.000	EACH
110	715-07794 WATER MAIN CONNECTIONS	4.000	EACH
111	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	186.000	TON
112	715-09064 VIDEO INSPECTION FOR PIPE	1,670.000	LFT
113	715-09843 BYPASS PUMPING	LUMP	LUMP
114	715-11360 INSERTION VALVE, 12 IN.	1.000	EACH
115	715-92544 WATER MAIN, DUCTILE IRON, 12 IN	73.000	LFT
116	715-94780 WATER MAIN, DUCTILE IRON, 6 IN	81.000	LFT
117	715-96669 WATER MAIN, DUCTILE IRON, 16 IN	1,672.000	LFT
118	716-07654 PIPE INSTALLATION, TRENCHLESS, 6 IN	122.000	LFT
119	716-09128 PIPE INSTALLATION, TRENCHLESS, 16 IN	198.000	LFT
120	718-52610 AGGREGATE FOR UNDERDRAINS	216.000	CYS
121	718-99153 GEOTEXTILES FOR UNDERDRAIN	2,039.000	SYS
122	720-01092 MANHOLE, J15, MODIFIED	8.000	EACH
123	720-03194 MANHOLE	3.000	EACH
124	720-08239 MANHOLE, J7, MODIFIED	1.000	EACH
125	720-08242 MANHOLE, L15, MODIFIED	1.000	EACH
126	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
127	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
128	720-45030 INLET, E7	2.000	EACH
129	720-45410 MANHOLE, C4	4.000	EACH
130	720-93501 MANHOLE, L4	3.000	EACH
131	720-95335 MANHOLE, M4	15.000	EACH
132	720-95422 MANHOLE, J4	4.000	EACH
133	720-96999 FIRE HYDRANT ASSEMBLY	4.000	EACH
134	720-98174 INLET, B15	5.000	EACH
135	720-99416 CATCH BASIN, B15	5.000	EACH
136	720-99417 CATCH BASIN, C15	6.000	EACH
137	725-08293 PIPE LINER, CURED-IN-PLACE, 36 IN	354.000	LFT
138	725-10245 PERPETUATION, EXISTING PIPE	7.000	EACH
139	725-11722 LINER PIPE, CCFRM, 42 IN	393.000	LFT
140	801-03290 CONSTRUCTION SIGN, C	10.000	EACH
141	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
142	801-06625 DETOUR ROUTE MARKER ASSEMBLY	33.000	EACH
143	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
144	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
145	801-07118 BARRICADE, III-A	540.000	LFT
146	801-11598 ARIES FIELD PROCESSOR FOR PCMS	3.000	EACH
147	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	3.000	EACH

CALL ORDER : 271

CONTRACT ID : R -35604-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT, ROUNDABOUT		
148	802-03896 BOLLARD	14.000	EACH
149	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	84.000	SFT
150	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	212.000	SFT
151	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	7.000	SFT
152	802-11364 POST	380.000	LFT
153	802-74080 OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	1.000	EACH
154	802-74085 OVERHEAD SIGN STRUCTURE, TWIN CANTILEVER, REMOVE	1.000	EACH
155	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.000	EACH
156	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
157	805-90187 CONDUIT, STEEL, GALVANIZED, 4 IN	206.000	LFT
158	807-02191 HANDHOLE, LIGHTING	10.000	EACH
159	807-02193 LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	12.000	EACH
160	807-03934 LIGHT STRUCTURE, REMOVE	12.000	EACH
161	807-03951 LIGHT POLE, ORNAMENTAL	12.000	EACH
162	807-04243 DECORATIVE POSTS AND LIGHTING	2.000	EACH
163	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	647.000	LFT
164	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	1,809.000	LFT
165	807-11354 LUMINAIRE, ROADWAY, METAL HALIDE, 250 WATT	12.000	EACH
166	807-86810 SERVICE POINT, II	1.000	EACH
167	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	504.000	LFT
168	807-86910 CONNECTOR KIT, UNFUSED	12.000	EACH
169	807-86915 CONNECTOR KIT, FUSED	12.000	EACH
170	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	37.000	EACH
171	807-86930 INSULATION LINK, NON-WATERPROOFED	27.000	EACH
172	807-86935 INSULATION LINK, WATERPROOFED	12.000	EACH
173	807-98336 WIRE, NO 1 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	296.000	LFT
174	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	6.000	SYS
175	808-06716 LINE, REMOVE	1,270.000	LFT
176	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	555.000	LFT
177	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	819.000	LFT
178	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	1,471.000	LFT
179	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	130.000	LFT
180	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	326.000	LFT
181	808-10042 TRANSVERSE MARKING MULTI-COMPONENT,	91.000	LFT
182	808-10049 LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN	710.000	LFT
183	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	24.000	LFT
184	808-10052 PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, (ONLY)	3.000	EACH
185	808-10058 LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN	283.000	LFT
186	808-10072 TRANSVERSE MARKINGS, MULTI-COMPONENT,	145.000	LFT
187	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	32.000	EACH
188	808-11481 LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	78.000	LFT
189	808-11691 LINE, THERMOPLASTIC, DOTTED, WHITE, 12"	102.000	LFT
190	808-11776 TRANSVERSE MARKINGS, MULTI-COMPONENT,	84.000	LFT
191	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	80.000	EACH
192	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	24.000	EACH

CALL ORDER : 281

CONTRACT ID : R -35688-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PIPE LINING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
9	202-96133 PIPE, REMOVE	6.000	LFT
10	205-06937 TEMPORARY SILT FENCE	1,307.000	LFT
11	601-06035 GUARDRAIL, RESET	500.000	LFT
12	621-03787 SEED MIXTURE, D	20.000	LBS
13	628-09409 MOBILE INTERNET SERVICE	9.000	MOS
14	628-11729 CELLULAR TELEPHONE TYPE A	1.000	EACH
15	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
16	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
17	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	9.000	MOS
18	715-46030 PIPE END SECTION, DIA 30"	2.000	EACH
19	715-46040 PIPE END SECTION, DIA 36 IN	8.000	EACH
20	725-11033 LINER PIPE THERMOPLASTIC CIRCULAR 4.9-5.0 SFT	166.000	LFT
21	725-11034 LINER PIPE THERMOPLASTIC CIRCULAR 7.0-7.1 SFT	938.000	LFT
22	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
23	801-06710 FLASHING ARROW SIGN	60.000	DAY
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
25	801-07117 TEMPORARY WORKSITE FLASHING LIGHT SIGN ASSEMBLY	4.000	EACH

CALL ORDER : 321

CONTRACT ID : RS-31335-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT CORRECTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02278 CURB, CONCRETE, REMOVE	23.000	LFT
13	202-52710 SIDEWALK, CONCRETE, REMOVE	31.000	SYS
14	203-02000 EXCAVATION, COMMON	908.500	CYS
15	203-02070 BORROW	3,146.000	CYS
16	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	15.000	TON
17	205-06937 TEMPORARY SILT FENCE	1,123.000	LFT
18	205-09543 NO 2 STONE	200.000	TON
19	207-09935 SUBGRADE TREATMENT, TYPE 1C	8,268.000	SYS
20	211-02050 B BORROW	150.000	CYS
21	211-09264 STRUCTURAL BACKFILL, TYPE 1	33.000	CYS
22	214-07203 GEOGRID, TYPE IB	800.000	SYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	135.000	TON
24	303-01180 COMPACTED AGGREGATE, NO. 53	1,985.000	TON
25	303-07449 COMPACTED AGGREGATE, NO. 73	449.000	TON
26	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	40.000	TON
27	304-07490 HMA PATCHING, TYPE B	223.000	TON
28	306-08042 MILLING, SCARIFICATION/PROFILE	75,281.000	SYS
29	306-08043 MILLING, TRANSITION	1,320.000	SYS
30	306-08432 MILLING, APPROACH	3,025.000	SYS
31	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
32	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	6,748.000	TON
33	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	847.000	TON
34	401-10258 JOINT ADHESIVE, SURFACE	30,169.600	LFT
35	401-10259 JOINT ADHESIVE, INTERMEDIATE	100.000	LFT
36	406-05520 ASPHALT FOR TACK COAT	22.100	TON
37	604-06070 SIDEWALK, CONCRETE	9.000	SYS
38	604-07894 CURB RAMP, CONCRETE, A	13.000	SYS
39	604-07902 CURB RAMP, CONCRETE, H	19.000	SYS
40	604-07903 CURB RAMP, CONCRETE, K	11.000	SYS
41	610-07486 HMA FOR APPROACHES, TYPE A	205.000	TON
42	610-07487 HMA FOR APPROACHES, TYPE B	250.000	TON
43	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
44	615-06520 MONUMENT, RE-ESTABLISH	5.000	EACH
45	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	4.000	EACH
46	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
47	621-02770 EROSION CONTROL BLANKET	1,192.000	SYS
48	621-06545 FERTILIZER	0.400	TON
49	621-06554 SEED MIXTURE, U	139.000	LBS

CALL ORDER : 321

CONTRACT ID : RS-31335-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT CORRECTION		
50	621-06565 MULCHING MATERIAL	1.900	TON
51	621-06570 TOPSOIL	708.000	CYS
52	621-06575 SODDING, NURSERY	42.600	SYS
53	628-09403 FIELD OFFICE, C	16.000	MOS
54	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	16.000	MOS
55	628-11729 CELLULAR TELEPHONE TYPE A	4.000	EACH
56	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
57	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
58	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	64.000	MOS
59	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	30.000	LFT
60	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	38.000	LFT
61	715-46005 PIPE END SECTION, DIA 15"	2.000	EACH
62	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
63	801-03290 CONSTRUCTION SIGN, C	10.000	EACH
64	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
65	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	2,999.000	LFT
66	801-06625 DETOUR ROUTE MARKER ASSEMBLY	33.000	EACH
67	801-06640 CONSTRUCTION SIGN, A	41.000	EACH
68	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
69	801-07119 BARRICADE, III-B	120.000	LFT
70	802-02475 SIGN, PANEL, RELOCATE	3.000	EACH
71	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	24.000	LFT
72	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
73	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	4.000	EACH
74	808-03439 TRANSVERSE MARKING THERMOPLASTIC	166.000	LFT
75	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	2.000	EACH
76	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	63,510.000	LFT
77	808-06716 LINE, REMOVE	2,999.000	LFT
78	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
79	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	5,990.000	LFT
80	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	39,958.000	LFT
81	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	192.000	LFT
82	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH
83	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH
84	808-75340 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
85	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1.000	EACH

CALL ORDER : 331

CONTRACT ID : RS-31610-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	398.000	SYS
13	202-02272 PAVED SIDE DITCH, REMOVE	240.000	LFT
14	202-02278 CURB, CONCRETE, REMOVE	283.000	LFT
15	202-02279 CURB AND GUTTER, REMOVE	680.000	LFT
16	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
17	202-62420 BRIDGE RAILING, REMOVE	410.000	LFT
18	203-02000 EXCAVATION, COMMON	179.000	CYS
19	203-08607 LINEAR GRADING	293.000	LFT
20	205-03371 SEDIMENT, REMOVE	10.000	CYS
21	205-06937 TEMPORARY SILT FENCE	1,171.000	LFT
22	207-09935 SUBGRADE TREATMENT, TYPE 1C	398.000	SYS
23	211-02050 B BORROW	101.000	CYS
24	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	135.000	TON
25	303-01180 COMPACTED AGGREGATE, NO. 53	225.000	TON
26	303-07449 COMPACTED AGGREGATE, NO. 73	300.000	TON
27	304-07490 HMA PATCHING, TYPE B	356.000	TON
28	306-08033 MILLING, ASPHALT, 1 IN	146,090.000	SYS
29	306-08036 MILLING, ASPHALT, 2 IN	246.000	SYS
30	306-08042 MILLING, SCARIFICATION/PROFILE	426.000	SYS
31	306-08043 MILLING, TRANSITION	747.000	SYS
32	306-08432 MILLING, APPROACH	4,190.000	SYS
33	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
34	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	12,113.000	TON
35	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	90.000	TON
36	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	126.000	TON
37	401-10258 JOINT ADHESIVE, SURFACE	52,276.000	LFT
38	401-11785 LIQUID ASPHALT SEALANT	71,234.000	LFT
39	406-05520 ASPHALT FOR TACK COAT	36.430	TON
40	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
41	601-02241 GUARDRAIL, REMOVE	200.000	LFT
42	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	100.000	LFT
43	602-06729 BARRIER DELINEATOR	14.000	EACH
44	605-06120 CURB, CONCRETE	293.000	LFT
45	606-07484 MILLED HMA CORRUGATIONS	106,851.000	LFT
46	610-07487 HMA FOR APPROACHES, TYPE B	346.000	TON
47	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	68.000	TON
48	612-60410 DRILLED HOLE FOR UNDERSEAL	1,135.000	EACH
49	615-06505 MONUMENT, B	2.000	EACH

CALL ORDER : 331

CONTRACT ID : RS-31610-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	3.000	EACH
51	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
52	616-02320 GEOTEXTILES	217.000	SYS
53	616-06405 RIPRAP, REVETMENT	163.000	TON
54	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
55	621-06570 TOPSOIL	38.000	CYS
56	621-06574 SODDING	249.000	SYS
57	628-09402 FIELD OFFICE, B	24.000	MOS
58	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	48.000	MOS
59	628-11730 CELLULAR TELEPHONE TYPE B	3.000	EACH
60	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
61	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	72.000	MOS
62	702-51863 FIELD DRILLED HOLE IN CONCRETE	284.000	EACH
63	703-06029 REINFORCING BARS, EPOXY COATED	123,705.000	LBS
64	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	820.000	EACH
65	704-51002 CONCRETE, C, SUPERSTRUCTURE	277.000	CYS
66	706-06351 CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.000	EACH
67	706-09962 RAILING, CONCRETE, PF-1	348.000	LFT
68	706-11404 RAILING, STEEL, PF-1	364.000	LFT
69	709-51821 SURFACE SEAL	LUMP	LUMP
70	710-09158 PATCHING CONCRETE STRUCTURES	100.000	SFT
71	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
72	801-03290 CONSTRUCTION SIGN, C	10.000	EACH
73	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	4,134.000	LFT
74	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	8,619.000	LFT
75	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	24.000	LFT
76	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
77	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
78	801-06710 FLASHING ARROW SIGN	200.000	DAY
79	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
80	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	2.000	EACH
81	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	811.000	LFT
82	801-53072 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
83	805-96014 SAW CUT, FULL DEPTH	293.000	LFT
84	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	619.000	LFT
85	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN	827.000	LFT
86	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	4,660.000	LFT
87	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	81,036.000	LFT
88	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	58,458.000	LFT
89	808-06716 LINE, REMOVE	1,332.000	LFT
90	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
91	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	410.000	LFT
92	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	410.000	LFT
93	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,842.000	LFT
94	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	944.000	EACH
95	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	139.000	EACH

CALL ORDER : 341

CONTRACT ID : RS-31684-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HMA OVERLAY, PREVENTIVE MAINTENANCE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02278 CURB, CONCRETE, REMOVE	693.000	LFT
11	202-02279 CURB AND GUTTER, REMOVE	170.000	LFT
12	202-52710 SIDEWALK, CONCRETE, REMOVE	212.000	SYS
13	202-93741 GUARDRAIL END TREATMENT, REMOVE	25.000	EACH
14	207-09935 SUBGRADE TREATMENT, TYPE 1C	703.000	SYS
15	208-05527 HMA FOR APPROACHES	423.000	TON
16	303-01180 COMPACTED AGGREGATE, NO. 53	462.000	TON
17	304-07490 HMA PATCHING, TYPE B	688.200	TON
18	306-08034 MILLING, ASPHALT, 1 1/2 IN	25,992.000	SYS
19	306-08042 MILLING, SCARIFICATION/PROFILE	53,750.000	SYS
20	306-08043 MILLING, TRANSITION	627.000	SYS
21	306-08432 MILLING, APPROACH	7,200.000	SYS
22	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
23	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2,200.000	TON
24	401-09970 QC/QA-HMA, 2, 64, SURFACE, 4.75 mm	2,270.000	TON
25	401-10258 JOINT ADHESIVE, SURFACE	40,128.000	LFT
26	402-07451 HMA WEDGE AND LEVEL, TYPE B	100.000	TON
27	406-05520 ASPHALT FOR TACK COAT	23.400	TON
28	601-01627 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
29	601-02241 GUARDRAIL, REMOVE	137.500	LFT
30	601-05071 GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, 7	1.000	EACH
31	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
32	601-94689 GUARDRAIL END TREATMENT, OS	24.000	EACH
33	604-07894 CURB RAMP, CONCRETE, A	20.100	SYS
34	604-07896 CURB RAMP, CONCRETE, B	12.500	SYS
35	604-07897 CURB RAMP, CONCRETE, C	70.100	SYS
36	604-07898 CURB RAMP, CONCRETE, D	13.000	SYS
37	604-07900 CURB RAMP, CONCRETE, F	43.800	SYS
38	604-07901 CURB RAMP, CONCRETE, G	9.600	SYS
39	604-08086 CURB RAMP, CONCRETE	41.900	SYS
40	605-06120 CURB, CONCRETE	693.000	LFT
41	605-06150 CURB AND GUTTER, C, CONCRETE	170.000	LFT
42	621-06575 SODDING, NURSERY	133.000	SYS
43	628-09402 FIELD OFFICE, B	6.000	MOS
44	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
45	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
46	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
47	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	12.000	MOS
48	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
49	801-03290 CONSTRUCTION SIGN, C	5.000	EACH



CALL ORDER : 341

CONTRACT ID : RS-31684-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HMA OVERLAY, PREVENTIVE MAINTENANCE		
50	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	5,608.000	LFT
51	801-06640 CONSTRUCTION SIGN, A	65.000	EACH
52	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
53	805-02328 SIGNAL CABLE, 1C/14 GA	1,948.000	LFT
54	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
55	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	722.000	LFT
56	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,422.000	LFT
57	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	164.000	LFT
58	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	43,824.000	LFT
59	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	54,436.000	LFT
60	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
61	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	90.000	LFT
62	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	126.000	LFT
63	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	253.000	LFT
64	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
65	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
66	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	381.000	EACH
67	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	381.000	EACH

CALL ORDER : 351

CONTRACT ID : RS-34486-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	304-07490 HMA PATCHING, TYPE B	200.000	TON
9	306-08042 MILLING, SCARIFICATION/PROFILE	6,000.000	SYS
10	306-08043 MILLING, TRANSITION	100.000	SYS
11	402-07433 HMA SURFACE, TYPE B	495.000	TON
12	406-05520 ASPHALT FOR TACK COAT	0.500	TON
13	615-97768 PARKING BARRIER, RESET	8.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	2.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 361

CONTRACT ID : RS-34564-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02278 CURB, CONCRETE, REMOVE	1,184.000	LFT
10	202-52710 SIDEWALK, CONCRETE, REMOVE	424.000	SYS
11	207-08263 SUBGRADE TREATMENT, TYPE IA	2,345.000	SYS
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,218.000	TON
13	303-01180 COMPACTED AGGREGATE, NO. 53	137.000	TON
14	304-07490 HMA PATCHING, TYPE B	2,275.000	TON
15	306-08034 MILLING, ASPHALT, 1 1/2 IN	30,806.000	SYS
16	306-08432 MILLING, APPROACH	5,789.000	SYS
17	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	2,542.000	TON
18	401-10258 JOINT ADHESIVE, SURFACE	13,961.000	LFT
19	406-05520 ASPHALT FOR TACK COAT	13.200	TON
20	503-05240 D-1 CONTRACTION JOINT	28.000	LFT
21	506-06333 PCCP PATCHING, FULL DEPTH	150.000	SYS
22	604-07894 CURB RAMP, CONCRETE, A	169.700	SYS
23	604-07897 CURB RAMP, CONCRETE, C	79.900	SYS
24	604-07898 CURB RAMP, CONCRETE, D	18.100	SYS
25	604-07902 CURB RAMP, CONCRETE, H	11.700	SYS
26	604-08086 CURB RAMP, CONCRETE	126.000	SYS
27	605-06120 CURB, CONCRETE	1,190.000	LFT
28	610-07487 HMA FOR APPROACHES, TYPE B	478.000	TON
29	621-06575 SODDING, NURSERY	185.000	SYS
30	628-09402 FIELD OFFICE, B	8.000	MOS
31	628-11730 CELLULAR TELEPHONE TYPE B	2.000	EACH
32	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
33	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
34	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	16.000	MOS
35	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
36	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	1.000	EACH
37	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
38	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
39	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	1,790.000	LFT
40	801-06625 DETOUR ROUTE MARKER ASSEMBLY	23.000	EACH
41	801-06640 CONSTRUCTION SIGN, A	67.000	EACH
42	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
43	801-07118 BARRICADE, III-A	56.000	LFT
44	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	21.000	LFT
45	802-07060 SIGN, SHEET, RELOCATE	3.000	EACH
46	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	946.000	LFT
47	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	278.000	LFT
48	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	2.000	EACH
49	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	520.000	LFT

CALL ORDER : 361

CONTRACT ID : RS-34564-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	5,850.000	LFT
51	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	5,850.000	LFT
52	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	181.000	LFT
53	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	9,947.000	LFT
54	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	115.000	LFT
55	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	290.000	LFT
56	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	1,191.000	LFT
57	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	8.000	EACH
58	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	3.000	EACH
59	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	90.000	EACH
60	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	90.000	EACH

CALL ORDER : 371

CONTRACT ID : RS-34572-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-02255 TREE, 18 IN, REMOVE	5.000	EACH
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	34.000	SYS
13	202-02278 CURB, CONCRETE, REMOVE	31.000	LFT
14	202-02279 CURB AND GUTTER, REMOVE	135.000	LFT
15	202-52710 SIDEWALK, CONCRETE, REMOVE	115.000	SYS
16	203-02000 EXCAVATION, COMMON	11.000	CYS
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	21.000	SYS
18	207-09935 SUBGRADE TREATMENT, TYPE 1C	184.000	SYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	20.000	TON
20	303-07449 COMPACTED AGGREGATE, NO. 73	102.000	TON
21	304-07490 HMA PATCHING, TYPE B	84.000	TON
22	304-07493 WIDENING WITH HMA, TYPE B	101.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN	80,307.000	SYS
24	306-08432 MILLING, APPROACH	2,706.000	SYS
25	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
26	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	6,626.000	TON
27	401-10258 JOINT ADHESIVE, SURFACE	33,059.000	LFT
28	402-05494 HMA RUMBLE STRIPS	45,904.000	LFT
29	406-05520 ASPHALT FOR TACK COAT	22.000	TON
30	412-09355 FOG SEAL	7,346.000	SYS
31	604-06070 SIDEWALK, CONCRETE	71.000	SYS
32	604-07897 CURB RAMP, CONCRETE, C	55.000	SYS
33	604-07901 CURB RAMP, CONCRETE, G	10.000	SYS
34	604-07902 CURB RAMP, CONCRETE, H	5.000	SYS
35	605-06120 CURB, CONCRETE	100.000	LFT
36	605-06140 CURB AND GUTTER, CONCRETE	141.000	LFT
37	610-07487 HMA FOR APPROACHES, TYPE B	224.000	TON
38	610-08446 PCCP FOR APPROACHES, 6 IN	21.000	SYS
39	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	5.000	EACH
40	621-06574 SODDING	59.000	SYS
41	628-09403 FIELD OFFICE, C	17.000	MOS
42	628-11730 CELLULAR TELEPHONE TYPE B	2.000	EACH
43	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
44	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
45	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	34.000	MOS
46	720-44000 CASTING, ADJUST TO GRADE	7.000	EACH
47	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
48	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	2,446.000	LFT
49	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	2,446.000	LFT

CALL ORDER : 371

CONTRACT ID : RS-34572-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	801-06640 CONSTRUCTION SIGN, A	27.000	EACH
51	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
52	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
53	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	4,386.000	LFT
54	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	48,566.000	LFT
55	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	22,193.000	LFT
56	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
57	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	623.000	LFT
58	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	394.000	EACH
59	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	11.000	EACH

CALL ORDER : 381

CONTRACT ID : RS-35311-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SURFACE TREATMENT, THIN HMA			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02279 CURB AND GUTTER, REMOVE	15.000	LFT
10	202-52710 SIDEWALK, CONCRETE, REMOVE	5.000	SYS
11	207-08267 SUBGRADE TREATMENT, TYPE IIIA	500.000	SYS
12	304-07491 HMA PATCHING, TYPE C	590.000	TON
13	306-08042 MILLING, SCARIFICATION/PROFILE	136,587.000	SYS
14	306-08043 MILLING, TRANSITION	1,000.000	SYS
15	306-11553 MILLING, ASPHALT, 3/4 IN	8,952.000	SYS
16	401-09941 QC/QA-HMA, 3, 70, SURFACE, 4.75 mm	6,185.000	TON
17	401-10258 JOINT ADHESIVE, SURFACE	50,000.000	LFT
18	406-05520 ASPHALT FOR TACK COAT	40.000	TON
19	604-06070 SIDEWALK, CONCRETE	5.000	SYS
20	604-07897 CURB RAMP, CONCRETE, C	28.000	SYS
21	604-07901 CURB RAMP, CONCRETE, G	150.000	SYS
22	605-06144 CURB AND GUTTER, A, CONCRETE	15.000	LFT
23	615-06505 MONUMENT, B	3.000	EACH
24	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
25	621-06574 SODDING	5.000	SYS
26	628-09402 FIELD OFFICE, B	9.000	MOS
27	628-11729 CELLULAR TELEPHONE TYPE A	1.000	EACH
28	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
29	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
30	628-11780 CELLULAR TELEPHONE SERVICE, 500 MINUTES	9.000	MOS
31	720-44000 CASTING, ADJUST TO GRADE	15.000	EACH
32	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
33	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	11,095.000	LFT
34	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	11,095.000	LFT
35	801-06640 CONSTRUCTION SIGN, A	35.000	EACH
36	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
37	808-05929 TRANSVERSE MARKING THERMOPLASTIC,	386.000	LFT
38	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	8,730.000	LFT
39	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	89,085.000	LFT
40	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	40,263.000	LFT
41	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	35.000	LFT
42	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	8.000	EACH
43	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH
44	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,023.000	EACH
45	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,030.000	EACH
46	808-97323 LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN	72.000	LFT

CALL ORDER : 391

CONTRACT ID : RS-35938-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PATCH AND REHAB PAVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	4,816.000	SYS
13	203-02000 EXCAVATION, COMMON	18,499.700	CYS
14	205-06933 TEMPORARY INLET PROTECTION	10.000	EACH
15	205-06937 TEMPORARY SILT FENCE	20,000.000	LFT
16	207-09935 SUBGRADE TREATMENT, TYPE 1C	73,465.200	SYS
17	211-09264 STRUCTURAL BACKFILL, TYPE 1	232.100	CYS
18	214-07202 GEOGRID, TYPE IA	10,000.000	SYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,977.300	TON
20	302-06464 SUBBASE FOR PCCP	4,513.700	CYS
21	303-01180 COMPACTED AGGREGATE, NO. 53	10,346.600	TON
22	304-07783 HMA PATCHING, TYPE D	250.000	TON
23	306-08037 MILLING, ASPHALT, 3 IN	426.700	SYS
24	402-07787 HMA WEDGE AND LEVEL, TYPE D	23.500	TON
25	402-10087 HMA FOR TEMPORARY PAVEMENT, D	8,158.400	TON
26	406-05520 ASPHALT FOR TACK COAT	5.400	TON
27	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
28	501-06325 QC/QA-PCCP, 14 IN	18,053.200	SYS
29	501-06727 CORING, PCCP	LUMP	LUMP
30	503-03489 RETROFITTED TIE BARS	2,020.000	EACH
31	503-05240 D-1 CONTRACTION JOINT	10,752.000	LFT
32	503-05310 TERMINAL JOINT	192.000	LFT
33	606-07484 MILLED HMA CORRUGATIONS	4,080.000	LFT
34	606-11064 MILLED PCCP CORRUGATIONS	15,740.000	LFT
35	610-07486 HMA FOR APPROACHES, TYPE A	132.000	TON
36	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
37	621-06545 FERTILIZER	1.000	TON
38	621-06553 SEED MIXTURE, R	850.000	LBS
39	621-06557 SEED MIXTURE, T	1,050.000	LBS
40	621-06565 MULCHING MATERIAL	24.000	TON
41	627-09331 SAFETY TERMINAL, TYPE TL-4	3.000	EACH
42	628-09401 FIELD OFFICE, A	12.000	MOS
43	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
44	628-11730 CELLULAR TELEPHONE TYPE B	2.000	EACH
45	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
46	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
47	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	24.000	MOS
48	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	15,590.000	LFT
49	715-91361 PIPE, PVC, 6 IN	1,602.000	LFT



CALL ORDER : 391

CONTRACT ID : RS-35938-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PATCH AND REHAB PAVEMENT		
50	718-06529 OUTLET PROTECTOR, 2	20.000	EACH
51	718-52610 AGGREGATE FOR UNDERDRAINS	1,571.200	CYS
52	718-99153 GEOTEXTILES FOR UNDERDRAIN	14,147.100	SYS
53	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
54	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
55	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	11,150.000	LFT
56	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	82,880.000	LFT
57	801-06640 CONSTRUCTION SIGN, A	68.000	EACH
58	801-06710 FLASHING ARROW SIGN	50.000	DAY
59	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
60	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	4,610.000	LFT
61	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	3,244.000	LFT
62	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH
63	804-06770 DELINEATOR POST	20.000	EACH
64	808-06716 LINE, REMOVE	33,450.000	LFT
65	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
66	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	11,320.000	LFT
67	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	11,320.000	LFT
68	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	2,830.000	LFT
69	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	142.000	EACH
70	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	142.000	EACH

CALL ORDER : 421

CONTRACT ID : B -32434-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT, CONCRETE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	202-96133 PIPE, REMOVE	180.000	LFT
12	203-02070 BORROW	484.000	CYS
13	203-51223 EXCAVATION, WATERWAY	643.000	CYS
14	205-03371 SEDIMENT, REMOVE	14.000	CYS
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	40.000	TON
16	205-06937 TEMPORARY SILT FENCE	1,540.000	LFT
17	207-08264 SUBGRADE TREATMENT, TYPE II	2,094.000	SYS
18	207-08267 SUBGRADE TREATMENT, TYPE IIIA	100.000	SYS
19	211-06467 AGGREGATE FOR END BENT BACKFILL	65.000	CYS
20	211-09264 STRUCTURAL BACKFILL, TYPE 1	10.000	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	994.000	TON
22	302-07455 DENSE GRADED SUBBASE	27.000	CYS
23	402-07432 HMA SURFACE, TYPE A	154.000	TON
24	402-07433 HMA SURFACE, TYPE B	8.000	TON
25	402-07435 HMA INTERMEDIATE, TYPE A	260.000	TON
26	402-07438 HMA INTERMEDIATE, TYPE B	19.000	TON
27	406-05521 ASPHALT FOR TACK COAT	1,982.000	SYS
28	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
29	601-05071 GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, 7	1.000	EACH
30	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
31	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	300.000	LFT
32	602-06729 BARRIER DELINEATOR	8.000	EACH
33	605-06095 CURB, INTEGRAL, B, CONCRETE	30.000	LFT
34	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	157.100	SYS
35	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
36	615-06490 RIGHT OF WAY MARKER	11.000	EACH
37	615-06505 MONUMENT, B	7.000	EACH
38	616-02320 GEOTEXTILES	949.000	SYS
39	616-06405 RIPRAP, REVETMENT	639.000	TON
40	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
41	621-02770 EROSION CONTROL BLANKET	4,500.000	SYS
42	621-06545 FERTILIZER	0.400	TON
43	621-06553 SEED MIXTURE, R	154.000	LBS
44	621-06557 SEED MIXTURE, T	136.000	LBS
45	621-06565 MULCHING MATERIAL	2.000	TON
46	621-06567 WATER	1.400	KGAL
47	621-06574 SODDING	386.000	SYS
48	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	70.000	EACH
49	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH

CALL ORDER : 421

CONTRACT ID : B -32434-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT, CONCRETE		
50	628-09402 FIELD OFFICE, B	8.000	MOS
51	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	8.000	MOS
52	628-09409 MOBILE INTERNET SERVICE	8.000	MOS
53	701-09558 TEST PILE, INDICATOR, PRODUCTION	128.000	LFT
54	701-09560 TEST PILE, INDICATOR, RESTRIKE	2.000	EACH
55	701-09739 PILE SHOE, HP 12 X 53	16.000	EACH
56	701-51195 PILE, STEEL H, HP 12 IN X 53	756.000	LFT
57	702-92857 CONCRETE, C, SUBSTRUCTURE	79.000	CYS
58	703-06029 REINFORCING BARS, EPOXY COATED	46,265.000	LBS
59	704-51002 CONCRETE, C, SUPERSTRUCTURE	122.000	CYS
60	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
61	706-51020 RAILING, CONCRETE, C	11.600	CYS
62	707-09865 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 36 IN X 49 IN	364.000	LFT
63	709-51821 SURFACE SEAL	LUMP	LUMP
64	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	42.000	LFT
65	715-05407 PIPE, END BENT DRAIN, 6 IN	80.000	LFT
66	715-46005 PIPE END SECTION, DIA 15"	2.000	EACH
67	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
68	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
69	801-06625 DETOUR ROUTE MARKER ASSEMBLY	11.000	EACH
70	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
71	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
72	801-07118 BARRICADE, III-A	48.000	LFT
73	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,600.000	LFT
74	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,600.000	LFT

CALL ORDER : 431

CONTRACT ID : B -32436-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	1,755.000	CYS
13	203-02070 BORROW	2,310.000	CYS
14	205-03371 SEDIMENT, REMOVE	40.000	CYS
15	205-06930 SPLASHPAD	8.000	TON
16	205-06932 TEMPORARY CHECK DAM, STRAW BALES	18.000	LFT
17	205-06936 TEMPORARY SEDIMENT TRAP	268.000	TON
18	205-06937 TEMPORARY SILT FENCE	537.000	LFT
19	205-06938 TEMPORARY SLOPE DRAIN	98.000	LFT
20	205-09543 NO 2 STONE	100.000	TON
21	206-51215 EXCAVATION, X	270.000	CYS
22	206-51817 SHEET PILING, STEEL	244.000	SFT
23	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,120.000	SYS
24	211-02050 B BORROW	700.000	CYS
25	211-09266 STRUCTURAL BACKFILL, TYPE 3	2,450.000	CYS
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	935.000	TON
27	302-07455 DENSE GRADED SUBBASE	20.800	CYS
28	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	221.000	TON
29	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	372.000	TON
30	401-10258 JOINT ADHESIVE, SURFACE	1,003.000	LFT
31	401-10259 JOINT ADHESIVE, INTERMEDIATE	1,003.000	LFT
32	401-11785 LIQUID ASPHALT SEALANT	2,006.000	LFT
33	406-05521 ASPHALT FOR TACK COAT	2,704.000	SYS
34	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
35	601-06037 GUARDRAIL END TREATMENT, I	4.000	EACH
36	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	175.000	LFT
37	602-06729 BARRIER DELINEATOR	4.000	EACH
38	603-92636 FENCE, CHAIN LINK, 72 IN	260.000	LFT
39	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	128.400	SYS
40	615-06490 RIGHT OF WAY MARKER	24.000	EACH
41	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
42	616-02320 GEOTEXTILES	1,914.000	SYS
43	616-06405 RIPRAP, REVETMENT	1,227.000	TON
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.000	EACH
45	621-06545 FERTILIZER	0.500	TON
46	621-06553 SEED MIXTURE, R	204.000	LBS
47	621-06557 SEED MIXTURE, T	450.000	LBS
48	621-06565 MULCHING MATERIAL	8.400	TON
49	621-06567 WATER	0.100	KGAL

CALL ORDER : 431

CONTRACT ID : B -32436-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-06574 SODDING	63.000	SYS
51	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	30.000	EACH
52	628-09401 FIELD OFFICE, A	18.000	MOS
53	701-02938 CORED HOLE IN ROCK, 24 IN	36.000	LFT
54	701-09558 TEST PILE, INDICATOR, PRODUCTION	73.000	LFT
55	701-09683 PILE SHOE, HP 12 X 74	8.000	EACH
56	701-95780 PILE, STEEL H, HP 12 IN X 74	159.000	LFT
57	702-51005 CONCRETE, A, SUBSTRUCTURE	45.800	CYS
58	702-51015 CONCRETE, B, FOOTINGS	24.400	CYS
59	702-92857 CONCRETE, C, SUBSTRUCTURE	18.600	CYS
60	703-06028 REINFORCING BARS	5,820.000	LBS
61	703-06029 REINFORCING BARS, EPOXY COATED	34,212.000	LBS
62	704-51002 CONCRETE, C, SUPERSTRUCTURE	81.200	CYS
63	706-11455 BRIDGE RAILING PEDESTRIAN FENCE	152.000	LFT
64	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
65	706-51020 RAILING, CONCRETE, C	15.600	CYS
66	707-09865 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 36 IN X 49 IN	232.500	LFT
67	709-51821 SURFACE SEAL	LUMP	LUMP
68	731-93945 FACE PANELS, CONCRETE	4,942.000	SFT
69	731-93946 WALL ERECTION	4,942.000	SFT
70	731-93947 LEVELING PAD, CONCRETE	250.000	LFT
71	801-03290 CONSTRUCTION SIGN, C	1.000	EACH
72	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
73	801-06625 DETOUR ROUTE MARKER ASSEMBLY	13.000	EACH
74	801-06640 CONSTRUCTION SIGN, A	13.000	EACH
75	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
76	801-07118 BARRICADE, III-A	48.000	LFT
77	801-07119 BARRICADE, III-B	48.000	LFT

CALL ORDER : 441

CONTRACT ID : B -33340-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ARCH BRIDGE REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
16	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
17	202-93741 GUARDRAIL END TREATMENT, REMOVE	1.000	EACH
18	203-02000 EXCAVATION, COMMON	1,093.000	CYS
19	205-06937 TEMPORARY SILT FENCE	787.000	LFT
20	207-09935 SUBGRADE TREATMENT, TYPE 1C	636.000	SYS
21	211-09266 STRUCTURAL BACKFILL, TYPE 3	781.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	131.000	TON
23	302-07455 DENSE GRADED SUBBASE	44.200	CYS
24	303-01180 COMPACTED AGGREGATE, NO. 53	101.000	TON
25	304-07491 HMA PATCHING, TYPE C	7.000	TON
26	304-07494 WIDENING WITH HMA, TYPE C	59.000	TON
27	306-08034 MILLING, ASPHALT, 1 1/2 IN	567.000	SYS
28	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	73.000	TON
29	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	71.000	TON
30	401-10258 JOINT ADHESIVE, SURFACE	848.000	LFT
31	401-10259 JOINT ADHESIVE, INTERMEDIATE	665.000	LFT
32	401-11785 LIQUID ASPHALT SEALANT	1,513.000	LFT
33	406-05521 ASPHALT FOR TACK COAT	1,087.000	SYS
34	412-09355 FOG SEAL	189.000	SYS
35	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
36	601-02241 GUARDRAIL, REMOVE	425.000	LFT
37	601-06035 GUARDRAIL, RESET	50.000	LFT
38	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
39	601-91147 GUARDRAIL END TREATMENT, RESET	1.000	EACH
40	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
41	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	100.000	LFT
42	601-99132 GUARDRAIL, TRANSITION, VH, 6 FT-3 IN SPACING	3.000	EACH
43	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	151.800	SYS
44	616-02320 GEOTEXTILES	61.000	SYS
45	616-05689 RIPRAP, CLASS 2	58.000	TON
46	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
47	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	966.000	SYS
48	621-06559 MULCHED SEEDING, R	644.000	SYS
49	621-08161 PERMANENT TURF REINFORCEMENT MAT	439.000	SYS

CALL ORDER : 441

CONTRACT ID : B -33340-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ARCH BRIDGE REHABILITATION			
50	628-09402 FIELD OFFICE, B	9.000	MOS
51	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	9.000	MOS
52	628-11730 CELLULAR TELEPHONE TYPE B	2.000	EACH
53	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
54	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
55	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	9.000	MOS
56	702-51005 CONCRETE, A, SUBSTRUCTURE	70.400	CYS
57	702-51015 CONCRETE, B, FOOTINGS	5.400	CYS
58	702-51863 FIELD DRILLED HOLE IN CONCRETE	136.000	EACH
59	703-06029 REINFORCING BARS, EPOXY COATED	25,692.000	LBS
60	704-51002 CONCRETE, C, SUPERSTRUCTURE	44.700	CYS
61	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
62	706-51020 RAILING, CONCRETE, C	0.200	CYS
63	709-51821 SURFACE SEAL	LUMP	LUMP
64	709-51821 SURFACE SEAL	LUMP	LUMP
65	710-09158 PATCHING CONCRETE STRUCTURES	30.000	SFT
66	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
67	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
68	801-06625 DETOUR ROUTE MARKER ASSEMBLY	29.000	EACH
69	801-06640 CONSTRUCTION SIGN, A	43.000	EACH
70	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
71	801-07118 BARRICADE, III-A	96.000	LFT
72	801-07119 BARRICADE, III-B	96.000	LFT
73	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	565.000	LFT
74	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	147.000	LFT
75	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	147.000	LFT
76	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	565.000	LFT
77	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	8.000	EACH
78	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	8.000	EACH

CALL ORDER : 451

CONTRACT ID : B -33947-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT AND WIDENING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	180.000	CYS
13	203-02070 BORROW	85.000	CYS
14	204-02290 SETTLEMENT PLATE	3.000	EACH
15	204-08415 STAKE, SETTLEMENT	3.000	EACH
16	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	37.000	TON
17	205-06936 TEMPORARY SEDIMENT TRAP	12.000	TON
18	205-06937 TEMPORARY SILT FENCE	735.000	LFT
19	205-09543 NO 2 STONE	200.000	TON
20	207-08263 SUBGRADE TREATMENT, TYPE IA	665.000	SYS
21	207-08267 SUBGRADE TREATMENT, TYPE IIIA	67.000	SYS
22	211-06467 AGGREGATE FOR END BENT BACKFILL	3.800	CYS
23	214-07203 GEOGRID, TYPE IB	100.000	SYS
24	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	329.000	TON
25	302-07455 DENSE GRADED SUBBASE	22.000	CYS
26	306-08034 MILLING, ASPHALT, 1 1/2 IN	265.000	SYS
27	406-05520 ASPHALT FOR TACK COAT	1.000	TON
28	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
29	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	2.000	EACH
30	601-02241 GUARDRAIL, REMOVE	160.000	LFT
31	601-09238 HAND DIG GUARDRAIL POST HOLES	10.000	EACH
32	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
33	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	162.500	LFT
34	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	126.000	SYS
35	610-07487 HMA FOR APPROACHES, TYPE B	170.000	TON
36	615-06505 MONUMENT, B	2.000	EACH
37	616-02320 GEOTEXTILES	128.000	SYS
38	616-05688 RIPRAP, CLASS 1	74.000	TON
39	616-06405 RIPRAP, REVETMENT	16.000	TON
40	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
41	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
42	619-93790 CLEAN AND EPOXY COAT EXISTING PILES	LUMP	LUMP
43	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
44	621-02770 EROSION CONTROL BLANKET	190.000	SYS
45	621-06559 MULCHED SEEDING, R	400.000	SYS
46	621-06567 WATER	0.500	KGAL
47	621-06574 SODDING	11.000	SYS
48	621-06575 SODDING, NURSERY	140.000	SYS
49	628-09402 FIELD OFFICE, B	5.000	MOS



CALL ORDER : 451

CONTRACT ID : B -33947-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT AND WIDENING		
50	701-09662 PILE, STEEL PIPE, 0.250 IN, 14 IN	348.000	LFT
51	701-09679 CONICAL PILE TIP, 14 IN	4.000	EACH
52	702-51005 CONCRETE, A, SUBSTRUCTURE	1.400	CYS
53	702-51863 FIELD DRILLED HOLE IN CONCRETE	12.000	EACH
54	703-01540 THREADED TIE BAR ASSEMBLY	74.000	EACH
55	703-06029 REINFORCING BARS, EPOXY COATED	20,815.000	LBS
56	704-51002 CONCRETE, C, SUPERSTRUCTURE	53.000	CYS
57	706-06351 CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.000	EACH
58	706-11404 RAILING, STEEL, PF-1	135.200	LFT
59	706-51020 RAILING, CONCRETE, C	7.300	CYS
60	709-51821 SURFACE SEAL	LUMP	LUMP
61	711-51038 STRUCTURAL STEEL	LUMP	LUMP
62	711-51864 DRILLED HOLE	66.000	EACH
63	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
64	711-96800 STUD SHEAR CONNECTORS	1,170.000	EACH
65	715-05407 PIPE, END BENT DRAIN, 6 IN	70.000	LFT
66	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
67	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
68	801-06625 DETOUR ROUTE MARKER ASSEMBLY	2.000	EACH
69	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
70	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
71	801-07118 BARRICADE, III-A	48.000	LFT
72	801-07119 BARRICADE, III-B	24.000	LFT
73	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	36.000	LFT
74	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	18.500	SFT

CALL ORDER : 461

CONTRACT ID : B -34414-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHAB-PIPE LINING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	205-06937 TEMPORARY SILT FENCE	587.000	LFT
10	616-02320 GEOTEXTILES	232.500	SYS
11	616-05689 RIPRAP, CLASS 2	210.000	TON
12	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
13	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	1,000.000	SYS
14	621-06559 MULCHED SEEDING, R	1,000.000	SYS
15	621-06626 MULCHED SEEDING, D	1,000.000	SYS
16	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
17	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
18	628-11730 CELLULAR TELEPHONE TYPE B	2.000	EACH
19	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
20	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
21	628-11781 CELLULAR TELEPHONE SERVICE, 750 MINUTES	6.000	MOS
22	725-11295 PIPE LINER, CURED-IN-PLACE, 54"	1,050.000	LFT
23	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
24	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
25	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH

CALL ORDER : 471

CONTRACT ID : B -34578-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK OVERLAY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-01066 HYDRO DEMOLITION	3,747.000	SYS
11	202-02240 PAVEMENT REMOVAL	201.000	SYS
12	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
13	202-51822 BRIDGE DECK OVERLAY, REMOVE	3,747.000	SYS
14	203-02000 EXCAVATION, COMMON	530.000	CYS
15	203-02070 BORROW	50.000	CYS
16	205-06937 TEMPORARY SILT FENCE	534.000	LFT
17	302-06464 SUBBASE FOR PCCP	40.000	CYS
18	302-07455 DENSE GRADED SUBBASE	65.000	CYS
19	306-08034 MILLING, ASPHALT, 1 1/2 IN	2,880.000	SYS
20	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	166.000	TON
21	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	188.000	TON
22	406-05521 ASPHALT FOR TACK COAT	178.000	SYS
23	502-06329 PCCP, 12 IN	160.000	SYS
24	503-03489 RETROFITTED TIE BARS	64.000	EACH
25	503-05240 D-1 CONTRACTION JOINT	96.000	LFT
26	503-05310 TERMINAL JOINT	96.000	LFT
27	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
28	601-02241 GUARDRAIL, REMOVE	100.000	LFT
29	602-06729 BARRIER DELINEATOR	24.000	EACH
30	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	381.000	SYS
31	616-02320 GEOTEXTILES	50.000	SYS
32	616-06405 RIPRAP, REVETMENT	30.000	TON
33	628-09402 FIELD OFFICE, B	14.000	MOS
34	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	14.000	MOS
35	628-11730 CELLULAR TELEPHONE TYPE B	2.000	EACH
36	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
37	628-11780 CELLULAR TELEPHONE SERVICE, 500 MINUTES	28.000	MOS
38	702-51863 FIELD DRILLED HOLE IN CONCRETE	64.000	EACH
39	703-06029 REINFORCING BARS, EPOXY COATED	71,903.000	LBS
40	704-51002 CONCRETE, C, SUPERSTRUCTURE	141.300	CYS
41	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
42	706-51020 RAILING, CONCRETE, C	80.300	CYS
43	709-51821 SURFACE SEAL	LUMP	LUMP
44	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	1,010.000	SFT
45	722-51842 BRIDGE DECK OVERLAY	3,740.000	SYS
46	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	120.000	CYS
47	722-60824 SURFACE MILLING	3,857.000	SYS
48	724-51925 STRUCTURAL EXPANSION JOINT, SS	174.000	LFT
49	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.000	EACH

CALL ORDER : 471

CONTRACT ID : B -34578-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK OVERLAY		
50	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
51	801-04308 ROAD CLOSURE SIGN ASSEMBLY	1.000	EACH
52	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	2,004.000	LFT
53	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	12,124.000	LFT
54	801-06625 DETOUR ROUTE MARKER ASSEMBLY	6.000	EACH
55	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
56	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
57	801-06710 FLASHING ARROW SIGN	140.000	DAY
58	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
59	801-07118 BARRICADE, III-A	96.000	LFT
60	801-07119 BARRICADE, III-B	180.000	LFT
61	801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1	320.000	LFT
62	801-08507 TEMPORARY TRAFFIC BARRIER, TYPE 1, ANCHORED	640.000	LFT
63	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH
64	808-01226 SNOWPLOWABLE RAISED PAVEMENT MARKER CASTING, INSTALL	12.000	EACH
65	808-06716 LINE, REMOVE	8,440.000	LFT
66	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	940.000	LFT
67	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	3,750.000	LFT
68	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	3,750.000	LFT
69	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	12.000	EACH
70	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	12.000	EACH

CALL ORDER : 541

CONTRACT ID : TM-35736-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LIGHTING MAINTENANCE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-06541 REMOVE	7.000	EACH
8	202-86946 HANDHOLE, REMOVE	4.000	EACH
9	628-09402 FIELD OFFICE, B	8.000	MOS
10	628-11730 CELLULAR TELEPHONE TYPE B	1.000	EACH
11	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
12	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MINUTES	8.000	MOS
13	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
16	807-02193 LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	1.000	EACH
17	807-02426 WIRE, THW, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	380.000	LFT
18	807-03745 WIRE, XHHW, NO 4 COPPER, IN CABLE DUCT, IN TRENCH, 1/C	5,200.000	LFT
19	807-03934 LIGHT STRUCTURE, REMOVE	1.000	EACH
20	807-11768 LIGHT POLE, ROADWAY, 40 FT. E.M.H., 20 FT. MAST	1.000	EACH
21	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	1,100.000	LFT
22	807-86910 CONNECTOR KIT, UNFUSED	12.000	EACH
23	807-86915 CONNECTOR KIT, FUSED	12.000	EACH
24	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	36.000	EACH
25	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.000	EACH
26	807-86930 INSULATION LINK, NON-WATERPROOFED	24.000	EACH
27	807-86935 INSULATION LINK, WATERPROOFED	8.000	EACH
28	807-86955 CABLE-DUCT MARKER	10.000	EACH

CALL ORDER : 551

CONTRACT ID : TM-35819-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LIGHTING MAINTENANCE		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 807-11772	LUMINAIRE, DIAGNOSIS AND REPAIR	437.000	EACH

