



TYPE D-1 SAWED CONTRACTION JOINT SEALANT OPTIONS

NOTES

1. Transverse joints shall be constructed perpendicular to the centerline with a maximum spacing of 18'-0" unless otherwise specified.
2. The configuration of the preformed elastomeric joint seal shall be a 9/16" to 5/8" wide seal with at least a five cell internal design. The seal height shall be 9/16" to 13/16" in uncompressed stage.
3. For transverse construction joints, the initial saw cut may be eliminated.

INDIANA DEPARTMENT OF TRANSPORTATION	
TRANSVERSE JOINT SEALS	
MARCH 2005	
STANDARD DRAWING NO. E 503-CCPJ-06	
	/s/ Richard L. VanCleave 3-01-05 DESIGN STANDARDS ENGINEER DATE
	/s/ Richard K. Smutzer 3-01-05 CHIEF HIGHWAY ENGINEER DATE